

3-82W
MAP NO. 64

SEC. 26 TWP. 33S RGE. 31W


STATE Kans. COUNTY SewardLOC. C NE NWOPERATOR Panhandle Dev. Co., Inc.

FT. FROM _____ LINE _____

NO. 2 FARM NAME Jury

FT. FROM _____ LINE _____

Kismet

ELEV. 2731 GR. 2738 DF. 2741 KBFR. 12/28/61 SPUD 12/26/61 COMP. 3/6/62CONT. McClellan Drlg., Rig #1 / GEOL. _____

NAME PRODUCING INTERVAL COMPLETION RECORD FROM - TO PERF. W/HOLES TREATMENT RECORD

a Miss 5832-76 84 1500A

b _____

c _____

d State Pot. Cal Fle I. P. OIL/DIST. 477 BO. WTR. NW GAS M.C.F.P.D. CHK. HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CPH _____ SIBHP _____

GOR. _____ GR. 36.8 PBD 5909 TD 5925

SIZE DEPTH CASING - CEMENT RECORD W/SAX. SIZE DEPTH W/SAX.

8-5/8" 1245 650

5 1/2" 5920 125

OPERATOR Panhandle Dev. Co. WELL NO. 2 Jury ELEV. 2741 KB

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

KB Tops & Datums

Tor 4300 CG 3054 - 313

Lans 4415 Hb 4264 -1523

Marm 5054 Tor 4298 -1557

Cher 5206 Lans 4420 -1679

St Gen 5695 Marm 5054 -2313

RTD 5925 -3184 Cher 5207 -2466

Morr 5535 -2794

DST #1 (Tor) 4304-25, Op St. Gen 5690 -2949

2 hrs, F to GB/2 hrs, LTD (St Gen) Not available

R 150' SWCM, IBHP 540#/30",

IFP 0#, FFP 55#, FBHP 385#/30"

DST #2 (Lans) 4440-95, Op 2 hrs, R 590' Mdy W + tr Oil,

IBHP 1395#, IFP 95#, FFP 325#, FBHP 1365#

DST #3 (St Gen) 5805-5925, Op 2 hrs, GTS/7", TSTM, R 5745'

Oil/NW, IBHP 1705#/30", IFP 985#, FFP 1580#, FBHP 1675#

/30"

DST #4 (Morr) 5565-5694, (Str Pkr) Op 1 hr., R 210' M, NS,

No IBHP, IFP 140#, FFP 440#, No FBHP, RTD 5925 (St Gen) Log,

5 1/2" @ 5920 w/125, MICT & CO 5909, 52/5863-76, 32/5832-40

(Ste. Gen) Pkr 5850, FU 750' oil/1 hr from 5832-40, ran
2" tbg (Str Pkr 5850-5886) A/500 M + 1000, 5863-76,
MP 2000# (Comm with 5832-40) Swb 85 BL - Kick off,
flo oil/NW, CO 5909 PBTB, State Pot: (Cal Flow) Flo 477
BOPD/NW, Miss 5832-76, Grav. 36.8°.

LIBERAL ELECTRIC LOG TOPS

2741 KB

Winfield 2708 (+33)
Council Grove 2990 (-249)
Heebner 4280 (-1539)
Toronto 4298 (-1557) tst SXWCM
Lansing 4420 (-1679) Tst mud + tr oil
Marmaton 5054 (-2313)
Morrow 5534 (-2793)
Chester 5608 (-2867)
Ste. Gen 5690 (-2949)
St. Louis 5796 (-3055) ¢ flo 477 BO
TD 5925