


3-295W
 MAP NO. 84 SEC. 26 TWP. 33S RGE. 31W
 STATE Kans. COUNTY Seward LOC. C SW SE
 OPERATOR Panhandle Dev. Co. FT. FROM _____ LINE _____
 WELL NO. 4 FARM NAME Simonson FT. FROM _____ LINE _____
 Kismet ELEV. 2728 GR. 2730 DF. 2733 KB.
 FR. 1/22/62 SPUD 1/18/62 COMP. 3/27/62
 CONT. McClellan Drlg. Tools /GEOL. _____



NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
	FROM - TO	PERF. W/HOLES			
a	<u>St Gen</u>	<u>5818-5901</u>	<u>80</u>	<u>3000A</u>	
b					
c					
d	<u>St. P (Cal Fl)</u>				
e	<u>I. P. OIL/DIST. 383 BQ. WTR.</u>	<u>tr</u>	<u>GAS</u>	<u>M.C.F.P.D.</u>	<u>CHK.</u> <u>HRS.</u> <u>24</u>
b	"	"	"	"	"
c	"	"	"	"	"
d					

D & A ()

SIP#	FI TP #	FI CP#	SIBHP
		<u>36.4°</u>	<u>5920</u>
GOR.		PBTD	
CASING - CEMENT RECORD		CEMENT RECORD	
SIZE	DEPTH	SIZE	DEPTH
<u>8-5/8"</u>	<u>1248</u>	<u>650</u>	
<u>5 1/2"</u>	<u>5908</u>	<u>75</u>	

OPERATOR Panhandle Dev. Co. WELL NO. 4 Simonson ELEV. 2733 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
	KB Tops & Datums				
Tor	4276		CG	3063	- 330
Kc	4401		Hb	4239	-1506
RTD (St Gen)	5920	-3187	Tor	4276	-1543
			Lans	4396	-1663
DST #1 (Tor)	4278-90,		Marm	5048	-2315
Op 1 hr., GTS/1", Ga	1630		Cher	5207	
Mcfgpd/1", Ga	2420 Mcfgpd		Morr	5526	-2793
/5", Ga	2630 Mcfgpd/10"		St. Gen	5677	-2944
Ga	2830 Mcfgpd/15", Ga		LTD (St Gen)	5918	-3185
	2980 Mcfgpd/20" & Stab				
	Rec no flu, IBHP 1325#/30", IFP 505#, FFP 630#, FBHP 1300#/30"				
DST #2 (St Gen)	5810-20, Op 2 hrs, GTS/6", TSTM, Oil to surf/68", R 4570' free oil + 630' M & GCO, IBHP 1625#/30" IFP 450#, FFP 1280#, FBHP 1585#/30"				
RTD 5920 (St Gen)	Log, LTD 5918, 5 1/2" @ 5908 w/75 sx, CO 5904, GRN Log, 28/5894-5901 (St Gen) § 30 BOPH/2 hrs, 500MA + 1000A (15%) F1 10 BOPH/3 hrs, F1 12 1/2 BOPH/5 hrs, 1 1/2" ck 40/5830-40, 12/5818-21 (St Gen) Kill well, Ran 2" tbg w/				

str pkrs @ 5815 & 5851, swb $\frac{1}{2}$ BOPH/NW/8 hrs, A/500 M + 1000 (15%),
Swb & flo 25 BOPH/NW/12 hrs, install 6 gas lift valves in 2"
tbg @ 5800 w/pkr @ 5791 $\frac{1}{2}$, swb 75 BO/NT,
State Pot: 9 hr flo rate, Cal flo 383 BOPD + tr wtr, G. 36.4°
fr Ste. Gen 5819-5901.

LIBERAL ELECTRIC LOG TOPS

2733 KB

Winfield 2715 (+18)
Council Grove 3004 (-271)
Heebner 4262 (-1529)
Toronto 4276 (-1543) Tst 2,980 MCF
Lansing 4396 (-1663)
Marmaton 5048 (-2315)
Morrow 5526 (-2793)
Chester 5626 (-2893)
Ste. Gen 5678 (-2945)
St. Louis 5772 (-3039) Flo 383 BOPD * tr wtr ϕ
TD 5920