


2 Copies

State KANSAS Field W.C.
 Company SKelly Oil Co County MEADE
 Farm EDIGER No. #1
 Sec. 11 Twp. 33 Range 27
 Spot NW NW SE
 Contractor _____
 Remarks _____
 Comm. 9/11/53 Comp. _____
 Elev. (DF) 2418 GL _____ KB _____ TD 6111 PB _____
 Pay 5686-91 5715-38



I.P. _____ Press. _____
 Casing Record: 13 3/8 _____ 7" _____
 20" _____ 10 3/4 _____ 5 1/2" _____
 16" _____ 8 5/8 _____

	Sample	Log
DST 4780-4823 nec	Neob 4450	
360' muddy sw BHP	LANS. 4624	
1520/20"	TORONTO 4460	
Ø 5686-5744 nec 58'	MAFM. 5240	
5' grey fm. gr. pyritic ss.	CLK. 5426	
11' grey fully xln shly ls	Mot. 5671	
13' grey shale.	Mot. 5673	
8' grey - fm → med xln shly ls.	ST ben 6062	
21' buff - med cr. xln fne vcl. ls.		
DST 5670-5744 op 1 hr. max g. 1,900 MCF nec 20' gcm.		
BHP 1875/20"		
Ø 5744-79- nec 35'		
10' soft cr. xln. fne lms.		
3' shly ls.		
14' grey shale.		
4 1/2' lms.		
DST 5712-79 op 45" g 750 MCF nec 70' mud		
BHP 1940		
Ø 5779-99 nec 20'		
5' dk grey fully xln. den lms.		
8' dk grey shale		

7' dk grey line.

DST 5803-5979 op 1 hr. rec 20' mud. BHP 200/

DST 5988-6043 op 45" rec 30' mud press?

DST 5966-6111 failed

DST 5966-6026 (5p) op 1 hr 30" rec 930' m.s.w

BHP 2650/20 RTD 6111 now sub.

RUCT Co to 6006 pg 135/5715-38 A/2000

g 6,125 MCF A/6000 45" g = 8,500 MCF A/6000

g 7,430 mcf (wet) set pl @ 5708 pg 30/5686-91

6 hr BD g 540 MCF (wet) ad x oil from

2000 x 2000 = 4 1/2 hr BD g 4,300 MCF ϕ

pl to 6004 5 hr BD g 5,600 MCF 5174/1675

4 hr BD g 7,010 MCF for completion