


*

State Ks. Field W. C.
 Company Skelly - Shamrock County Meade
 Farm D.E. Thiessen No. 1
 Sec. 8 Twp. 33 Range 27

Spot 1250 fm S + 2310 fm E

Contractor Wentworth

Remarks skelly 50%
sham 50% gas mts. 6300'



Comm. 11/23/58 Comp. 1/14/59

Elev. 445 DF 2443 GL 2436 KB TD 5840 PB 5700

Pay Mor ss 5695-99, 5690-92

I.P. 2.7414 Press. SIP 1660#

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 58.33/200

16" 8 5/8 1403/600

Loc	Sample	Log
NOV 25 spcl	Hb 4418	Hb ⁻¹⁹⁶⁵ 4408
TFO 1403	Lan 4601	Lan ⁻²¹⁵¹ 4594
WOC	Man 5224	Man 5206
DEC 3 3906	Chrs 5410	Chrs 5401
DEC 10 5070	Mor 5686	Mor ⁻³²³¹ 5674
DEC 17 5570	Chrs	Chrs ⁻³²⁴⁶ ^{corr} ⁵⁹ 5699
DEC 30 E 5692-5728	Mor ss 5699	⁽¹³⁾ 5702
rec 34' 2'ls, 3 1/2' sh,	5702	Chrs ⁻³²⁸⁰ 5723
2 1/2' ss green-white	Chrs 5722	
fine grained fair per		
glauc. yd odor gas		
nustain, 2' sh 1'ls		
1 1/2' ss as above,		
6 1/2' ls glauc sdy sl. odor		
3' sh, 2'ls, 2'ls w/odor		
8'ls.		

OST 5681-5728 op 1' gts 9"

tstm 98 mcf/30", 196 mcf/60"

rec 180' gcm FP 73 BHP 1970/20

DST 5736-85 op 1' rec 90'm

FP 12-24 SIP 65/20

DST 5784-5840 op 1' rec 30'm

FP 44 SIP 75/20 RTD 5840

SJ 5830 ~~mg 5 1/2~~ ~~mg.~~ (over)

MICT CO 5797

P16/5714-18 12/5709-12

A/500m 5'g 300mf + 20 G WPH

Fx 15 A₆ X 2.5 sd 5'2' 8'g

867mf w/50 G WPH + 5'g

JAN 7

5 1/2' g 867mf w/40 G WPH:

p1 5728 P16/5695-99 8/5690-92

g 300mf w/50 G WPH PB 5701

~~SD to Weather.~~

JAN 14

5'g 206mf na mtr A/250m

6'g 679mf 35W Fx 6.3 dia X 3 sd.

8'g 2, 120mf + 100 Gld PH

8'g 2, 120mf w/sli sp.

4 SICP 1475 2" T SICP 1660

3'g 2, 740mf FCP 525

g. 2, 740mf SIP 1660⁺

Mar 55 5695-99

5690-92

AMARILLO TOPS

2443 DF

Heebner 4418 (-1975)

Douglas 4422 (-1979)

Lansing 4570 (-2127)

Morrow 5672 (-3229) T 54'

"S-3" 5683 (-3240) 26/37, G 2,700 MCF

Chester 5726 (-3283) NS