


*

State Ks Field McKINNEY
 Company GRAHAM-MICH. County MEADE
 Farm M. A. HORNER "B" No. 1
 Sec. 13 Twp. 33 Range 27

Spot NW
 Contractor Co. TOOLS
 Remarks P.D. 5600



Comm. 9-21-57 Comp. 10-30-57
 Elev. DF 2335 GL 2327 KB TD 5780 PB
 Pay MOR. 5642-47 MISS-5622-5704

I.P. g 12,000 MCF Press. SITP 825/20"
 Casing Record: 13 3/8 7"
20" 10 3/4 5 1/2" 5780/200
16" 8 5/8 525/335

Log	Sample	Log
SEP 2 8 5/8 LC @ 2663		MOR 5629
OCT 2 4 1/2		" sd 5640
OCT 9 5 5/8		<u>CHESTER 5676</u>
OCT 16 DST 5628-5720		
op 1 hr. GTS 15"		
g 1,250 MCF rec. 300'		
HGCM FP 811-949		
BHP 1986/30" RTD 5780		
ream log 5 1/2		
MICT		
OCT 23 Co. pt 56/5692-5704		
MA/500 g 1,250 MCF		
FR/8000 sd/8000		
g 5,500 MCF pt 22/5642-47		
MA/500 FR/5000		
sd/5000 g 6,300 MCF <u>WST</u>		
OCT 30 san T g 12,000 MCF thru T FTP 160		
SITP 825/20" <u>waiting on</u>		

⊕

AMARILLO TOPS

2335 KB

Winfield 2675 (-340)

Heebner 4400 (-2065)

Lansing 4570 (-2235)

Morrow 5629 (-3294)

"S-2" Sd 5640 (-3305) T 11', por 11', tst'd SSG

Chester 5665 (-3330) \emptyset 12,000 MCF

TD 5780 (-3445)