


State Kansas Field Thiessen GA
 Company Skelly Oil Company County Meade
 Farm C. A. Isaac No. 1
 Sec. 18 Twp. 33S Range 27W

Spot 1250' fr N & EL

Contractor 5900' Chester

Remarks



Comm. 11/21/59 Comp. 1/13/60
 Elev. DF 2437 GL KB TD 5920 PB 5782
 Pay Mor 5752-57, 5760-66

I.P. COF 22-982A Press. RP 1650
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 5919/125
 16" 8 5/8 1399/900

LOCATION	Log	Datum
NOV 25 sp. TTD 1400 mg csg	Hb 4456	
DEC 2 csg. ϕ 3445	kan 4644	
DEC 9 Hb 4456 kan 4646	Mrm 5276	
ϕ 4910	Chero 5452	
DEC 16 Mrm 5160 Chero	Mor 5736	-3247
5454 Mor 5736	ss 5754	-3265
TTD 5757 to ϵ	68	14'
DEC 23 ϵ 5757-95 m. 38'	Ch. 5796	-3307
1' ls oliv. ad.		
6" ss shly glauc.		
6" sh blk		
3' ss vshly glauc		
6" ls v fss		
6" sh sdy		
2' ls brn sdy		
1' sh blk sdy		
1 1/2' ls sdy		
4 1/2' sh blk rotten		
1' ls dns grn.		
3 1/2' ls blk shly dns		
1' cht.		
11' ls blk dns		
2' sh blk rotten		

2' ls med xln
1' ls brn sli por
1 1/2' ls fn xln dng.

DST 5736 - 95 q 7" gts 1"
g 1, 190 mcf/13" g. 3, 789 mcf/17"
mc 5' Cond. 151P 1990/20"
FP 750 - 900 FSIP 1960/20"

RTD 5920 SJ.

DST 5795 - 5920 q 1 in. mc 75' m
151P 315/20" FP 35 - 75 FSIP 215/20"
cag. WOL.

DEC 30 C05782 GR P24/5760-66
20/5752-57 2'BD 4, 292 mcf
A/500m 6'BD 4, 950 mcf thru cag.
14' SICP 1650 FX 10 Ac X10, sd
2" Hg 4 1/2' BD 10, 900 mcf +14
FCP 1330 8' SICP 1650
2 1/2' BD 9, 360 mcf SI WOT
JAN 1'8 1 COF 22, 992 mcf
RP 1650

Nov 5752-57
5760-66