

*

State KS Field McKINNEY
Company GRAHAM - MICH County MEADE
Farm MERTON - HORNER "C" No. 1 C
Sec. 14 Twp. 33 Range 27

Spot NE



Contractor CO. TOOLS

Remarks ^{P.D.} 5700' SKELLY INT

Comm. 1-27-58 Comp. 4-16-58

Elev. DF 2412 GL 2410 KB TD 5805 PB 5726

Pay P & A

I.P. Press.

Casing Record: 13 3/8 7"

20" 10 3/4 602/228 5 1/2" 5804/80

16" 8 5/8

<u>Ø 419</u>	Sample	Log
<u>FEB 5</u> <u>10 3/4</u> <u>Ø 2562</u>	<u>H6</u> <u>4476</u>	<u>Morish</u> <u>5700</u>
<u>FEB 12</u> <u>Ø 2188</u>	<u>Iron</u> <u>4485</u>	<u>" ss</u> <u>5714-30</u>
<u>FEB 19</u> <u>Ø 5329</u>	<u>Lens</u> <u>4649</u>	<u>Ches</u> <u>5740</u>
<u>FEB 26</u> <u>DST</u> <u>5674-5785</u>		
<u>sts 4"</u> , <u>op 90"</u> , <u>10"</u> , <u>62 wcl</u>		
<u>20"</u> - <u>68</u> <u>wcl</u>		
<u>30"</u> - <u>88</u> <u>"</u>		
<u>40"</u> - <u>116</u> <u>"</u>		
<u>50"</u> - <u>"</u> <u>"</u>		
<u>60"</u> - <u>124</u> <u>"</u>		
<u>70"</u> - <u>132</u> <u>"</u>		
<u>80"</u> - <u>143</u> <u>"</u>		
<u>90"</u> - <u>"</u> <u>"</u>		
<u>Dev</u> <u>175'</u> <u>gcm</u>		
<u>FP</u> <u>45-70</u>		
<u>BHP</u> <u>1685/30"</u>		
<u>BHP</u> <u>1855/30"</u>		
<u>RTD</u> <u>5805</u> , <u>org</u> , <u>WOC</u>		

MAR 5 MAR 12 P/12 5751-54
Ac 500 man, 10 gals water/hour
50 w/300 5x WOC
MAR 19 P/8 5771-73
8 5776-78

Sunda 18 gals x w/hr w/ USSG
phs 5736, SQ w/ 300 SX
P/24 5720-26, g. 130 mcf + 5 gals
wtr/hr. - 2 1/2', Ac 500 ma,
g. 823 mcf + 16 gals wtr/held

found channelling 5716-40

phs 5700, SQ w/ 265 SX
P/20 5719-24, Ac 500 ma, no gas
tstg 1 1/2 B.W.P.H., SQ w/ 200 SX

MAR 28 CO. 5731

P/40 5719-24 Suddry - USSG
Ac 500 ma, 6' tot 30 gals wtr/hr
SSG SQ w/ 195 SX, w/c

APR 1 CO. 5728, prep. pf

APR 9 P/12 5721-24 no gas

no - P/12 " " g. 100 mcf + 10-15
gals wtr/hr, frac 8000 ac. x 5000 sd
Ac 4000, g. 130 mcf + 1 B.W.P.H.
doc.

P/1 5722 Bear gum

~~10 gals coal mat~~, g. 280 mcf +
1 B. fl/hr, Ac 500 ma, w/c

APR 16 g. 350 mcf + 30 gals wtr

CO. 5726 vibro-frac (5721-26)

2 g. - 1.4 M

2 1/2' g. - 1,120 mcf, ST-2 1/2'

RP-700, op. 2 1/2' - g. 523 mcf +

30 gals wtr, prep vibro-frac

APR 23

didn't " "

P & A

