


State Kansas Field McKinney
 Company Shamrock Oil & Gas County Meade
 Farm F. Classen "C" No. 1
 Sec. 4 Twp. 33S Range 27W

Spot 1250' fr S&WL

Contractor 5850'

Remarks



Comm. 10/8/59 Comp. 12/9/59

Elev. 445 DF 2358 GL KB TD 5720 PB 5687

Pay MOR 5586-94

CGF 1.64 MA + 1/4 Cor.
 I.P. 517P 1707

Casing Record: 13^{3/8} 7"

20" 10^{3/4} 4^{1/2}" 5720/100

16" 9^{5/8} 1553/900

LOCATION	Log	Datum
SEP 3 0	C.G. 2929	
OCT 7 4	B/H 4354	
OCT 1 4	TDR 4366	
OCT 2 1	Lan 4534	
NOV 2 8	Mor 5570	-3212
NOV 4	ss 5585	-3227
12' sh.	98	13'
3' silt	<u>Miss 5617</u>	-2259
2' ls.		
4' ss		
1' ls		
3' ss		
2' ls		
2' ss		
15' sh		
3' ss		
DST 5563-5613 of 2 hrs 10 min		
gts 1' 16" 1' 20" g. 26 mat		
2' 10" g 47 mat 1 hr 120'		
gcm FP 35-55		
SIP 1925/30"		
E 5613-56 me 40'		
0.5' ss + sh		

4.5 ls
4 ls sdy v foss
17.5 ls shly
4.5' sh
2' ls.
1.5 sh
3.5 ls
2 ls tsh

RTD 5720 Sj. 5724

NOV 11 WOO

log CO 5687 P 32/5586-94
2 3/8" T 5600 A/500 5" SIP 400
KO g. 396 mcf + sp Cond + AW
FCP 100 targ.

NOV 18

pull tkg A/500 (5%) Ac Fx 20 x 10
tkg 5600 6' BD g. 1,024 mcf + 10 GAUPH
w/ tr dist 3/4" db FCP 240 MOSU.
SI 4 day SIP 1660 CP 1670
277 Bhd to rec.

NOV 25

SI WOT

DEC 2

DEC 9

4pt BPT COF 1,640 mcf
+ tr Cond SIP 1707
SICP 1714 SIBHP 2030
Mar 5586-94