

CONFIDENTIAL

ORIGINAL

RECEIVED

KCC

FEB 25 2004

FEB 23 2004

KCC WICHITA

CONFIDENTIAL

WELL REPORT

***McCoy Petroleum Corporation
Isaac Trust "C" Unit #1-35
50' W of E/2 NW NE
Section 35-33S-28W
Meade County, Kansas
API #15-119-21,121***

MPC #799 (03-41)

Spud: 11-30-03

Contractor: Val Energy, Inc., Rig #2

Geologist: Dave Clothier

Elevations: 2476' GL 2486' KB (All measurements from KB)

11-30-03 MIRT. Spud well at 6:00 PM.

12-01-03 TD 842'. Waiting on water. Drilling 12 1/4" hole. Lost returns at 582'. Well blew out at 647'. Died in 30 minutes. Dry drilled remaining surface hole to 935'. Ran 20 joints of new 8 5/8" 23# L.S. casing (915.64'). Strapped bottom 3 joints and welded collars on 17 joints. Set casing at 921' KB. Shoe joint 45.68'. Top of insert at 875.32'. Baskets at 594.45' and 641.29'. Acid Services cemented with 225 sacks of 11.5 ppg A-Con Blend with 3% CC and 1/4# Cellflake/sk, yielding 2.91 ft³/sk followed by 150 sacks of 15.6 ppg Common with 2% CC, 2% gel and 1/4# Cellflake/sk, yielding 1.27 ft³/sk. Cement did not circulate. Plug down at 3:30 PM. Pressured up on plug to 500# and casing jumped and lost pressure. Could pump 1.75 BPM @ 175#. Shut down. Casing standing full of water. No flow back. Waited 4 hrs and ran temperature survey. Top of ratty cement @ 520' and solid top of cement @ 620'. Ran 1" to 430'. Established circulation. Acid Services cemented with 200 sacks of 12.5 ppg common cement. Lost circulation while pumping, cement did not circulate. POOH with 1" and wait 4 hrs. Ran

CONFIDENTIAL

ORIGINAL

McCoy Petroleum Corporation
Isaac Trust "C" Unit #1-35
50' W of E/2 NW NE
Section 35-33S-28W
Meade County, Kansas

KCC

FEB 23 2024

CONFIDENTIAL

1" to 400'. No circulation. Acid Services cemented with 200 sacks of 12.5 ppg common cement. No circulation. Could not pull 1". Parted 1 joint down. Left 375' of 1" in hole.

12-02-03 TD 935'. Cementing surface casing. WOC. Ran 1" to 125'. Acid Services cemented with 50 sacks of 12.5 ppg common cement. Cement circulated to surface. WOC. Drilled out surface casing at 9:00 PM.

12-03-03 TD 1445'. Drilling ahead.

12-04-03 TD 2545'. Drilling ahead.

12-05-03 TD 3130'. Running short trip and TOOH for DST #1 in Council Grove 'A'.

Council Grove 'A' Porosity 3115-3125': Ls., lt. crm., f. xtl., foss., chlky. in prt., fr./gd. vug. por., VSSGB, dull yllw. fluor., no gas kick. (gas detector may not be functioning properly)

DST #1 3093-3130' (Council Grove "A") .
Open 30" Shut-in 45" Open 30" Shut-in 30"
1st Op: Weak surface blow, died in 20"
2nd Op: Weak surface blow, died in 20"
Rec.: 60' Mud
IFP: 22/34# FFP: 38/44#
SIP: 844/783#

12-06-03 TD 3350'. Drilling ahead.

12-07-03 RTD 3450'. LTD 3447'. Log-Tech ran Dual Induction and Density/Neutron logs. Acid Services **plugged well** with 115 sx of 60/40 pozmix with 6% gel as follows. Spotted 50 sx @ 930', 30 sx @ 480', 10 sx @ 40', 15 sx in rathole and 10 sx in mousehole. Plug down at 3:45 AM.

CONFIDENTIAL

ORIGINAL

McCoy Petroleum Corporation
Isaac Trust "C" Unit #1-35
50' W of E/2 NW NE
Section 35-33S-28W
Meade County, Kansas

RECEIVED
FEB 25 2004
KCC WICHITA

KCC
FEB 23 2004
CONFIDENTIAL

SAMPLE TOPS

Structure compared to

McCoy Petroleum Corporation
Isaac Trust C Unit #1-35
50' W of E/2 NW NE
Sec. 35-33S-28W
2486 KB

McCoy Petroleum
Isaac Trust 'B'#1-35
150' SW of SW SE
Sec. 35-33S-28W
2472 KB

Ensign Operating
Wiens #1-35
C SW NW
Sec. 35-33S-28W
2491 KB

Herrington	2681 (-195)	+26	+10
Krider	2716 (-230)	+23	+9
Winfield	2762 (-276)	+28	+11
Towanda	2832 (-346)	+31	+3
Wreford	3004 (-518)	+28	+3
Council Grove "A"	3115 (-629)	+29	-2
Council Grove "B"	3138 (-652)	+32	+1
Council Grove "C"	3158 (-672)	+29	Flat
Council Grove "D"	3181 (-695)	+29	+2
RTD	3450 (-964)		

LOG TOPS

Structure compared to

McCoy Petroleum Corporation
Isaac Trust C Unit #1-35
50' W of E/2 NW NE
Sec. 35-33S-28W
2486 KB

McCoy Petroleum
Isaac Trust 'B'#1-35
150' SW of SW SE
Sec. 35-33S-28W
2472 KB

Ensign Operating
Wiens #1-35
C SW NW
Sec. 35-33S-28W
2491 KB

Herrington	2685 (-199)	+22	+6
Krider	2717 (-231)	+22	+8
Winfield	2764 (-278)	+26	+9
Towanda	2834 (-348)	+29	+1
Wreford	3012 (-526)	+20	-5
Council Grove "A"	3116 (-630)	+28	-3
Council Grove "B"	3138 (-652)	+32	+1
Council Grove "C"	3168 (-682)	+19	-7
Council Grove "D"	3190 (-704)	+20	-7
LTD	3447 (-961)		