

8-302W

MAP NO.

SEC. 2 TWP. 33S RGE. 28W

STATE Kans COUNTY Meade

LOC. C NW SW

OPERATOR Panhandle Dev. Co., Inc.

FT. FROM LINE

WELL NO. 1 FARM NAME Nichols "A"

FT. FROM LINE

OOO Borchers, No

ELEV. 2525 GR 2532 DF 2535 KB

FR. 4/30/62 SPUD 4/9/62 COMP. 8/28/62

CONT. McClellan Drlg. Tools /GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a. Morrow	5669-72½	8 Jet	1000A&Frac
b.			
c.			
d. Del Ga			

a I. P. OIL/DIST.	WTR.	GAS	1700	M.C.F.P.D.	CHK.	HRS.	24
b. "	"	"	"	"	"	"	"
c. "	"	"	"	"	"	"	"
d.							

SIP# FI TP # FI CP# SIBHP

GOR. GR. PBD TD 5813

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
8 5/8" @	1221	600			
4½" @	5794	150			

OPERATOR Panhandle Dev. Co. WELL NO. 1 Nichols "A" ELEV. 2535 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			KB Tops & Datums		
Morr Sd	5658-81		Hb	4410	-1875
			Tor	4460	-1925
RTD	5810	-3275	Lans	4606	-2071
			Chero	5364	-2829
DST #1 (Morr Sd) 5658-90, Op 90",			Morr	5613	-3078
GTS/6", Ga 215 MCFGPD/10", Stab			Morr sd	5667-82	-3132
@ 714 MCFGPD/NT, R 15' Mud,			Miss	5769	-3234
IBHP 1982#/30", IFP 85#, FFP			LTD(Miss)	5813	-3278
125#, FBHP 1982#/30".					
RTD 5810. Log. 4½" @ 5794 w/150 sx, 4-way jet 5669, 4 way jet 5672½ (Morr) no sho nat, 500 MA & 500 A(15%) MP 1250-500#, TP 600#, on vac 15", Flo 735 MCFGPD w/tr Dist & AW, 12 hrs. Frac (10,000 GA(3%) & 10,000# sd) MP 1850-350#, on vac 45", Flow 3038 MCFGPD/12 hrs, Kill Well w/1000 acid & 2000' GSW, Set tbg. 4 point test. Max Flo rate Ga 1574 MCFGPD, SICP 1667#, SITP 1661#, Indicated OF Ga 2900 MCFGPD, FTP 1285#, FCP 1372#, Deliverability 1700 MCFGPD, Morr 5669-72½. 8/17/62.					

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2535 KB

Heebner 4430 (-1895)

Toronto 4456 (-1921)

Lansing 4606 (-2071)

Marmaton 5258 (-2723)

Morrow 5614 (-3079)

"S-2" 5668 (-3133) 10/14; ϕ 1.7 M

Chester 5768 (-3233)

TD 5810