

19-33-29W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

GULF OIL CORPORATION &
Company-CHAMPLIN REFINING CO.
Farm-F. E. Banker No. 1

SEC. 19 T. 33 R.29W
C SW NE

Total Depth. 5970 PBSD 5851
Comm. 1-19-56 Comp.2-15-56
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 8-18-56

County Meade
KANSAS



Elevation. 2692 DF

Production. Dry

CASING:
8 5/8 @ 1499' w/ 850 sx cmt.
4 1/2 @ 5933' w/ 200 sx cmt.

Figures Indicate Bottom of Formations.

clay & sand	475	Acid. Perf. 5835-46 w/ 500 gal NA
red bed & sand	1005	Fracked w/ 10,500 gal gelled kero
red bed, shale & sand	1270	12,000 # sand
red bed	1465	Acid Perf. 5800-06w/ 500 gal NA
anhydrite & lime	1500	Acid Perf. 5820-27
shale & sandy anhydrite	1618	
red bed, shale & salt	2150	Perf. 4 JSPF/5835-46, fracked w/
shale, salt & anhydrite	2200	15,000 gal gelled kero. & 22,500#
shale & anhydrite streaks	2333	sand
lime & shale	2505	
shale & lime streaks	2605	
shale & lime	2711	
lime	3213	
broken lime	3298	
chalk & lime	3316	
lime & shale	3398	
shale & lime streaks	3515	
shale & lime	3970	
lime	4032	
lime & shale streaks	4112	
lime & shale	4275	
shale	4360	
shale & lime	4443	
shale	4460	
lime & shale	4579	
chalky lime & shale	4650	
shale & lime	4802	
lime	5087	
lime & shale	5170	
lime	5353	
lime & shale	5456	
lime	5565	
lime & chert	5605	
lime	5782	
sand	5808	
coring	5858	
shale	5862	
shale & lime	5980	
Corrected (10' error 5151')	5970	
Total Depth		

Plugged back to 5851

TOPS:

Heebner	4461
Lovell (Toronto)	4495
Lansing	4634
Skiatook	5108
Marmaton	5280
Cherokee	5464
Atoka-Morrow	5768
Morrow sand	5798
Mississippian	5868

Perf. 4 JSPF/5800-06, 5820-27, 5835-46,
500 gal mud acid, Fracked w/ 20,000
gal gelled Kero. 30,000# sand