



DST #3 (Miss-Chest) 5656-5723, op 1 hr, WB & died in 45",  
rec 30' Mud, IBHP 50/30, FP 12-12, FBHP 12/30:  
RTD 5800, log, ran 5½" @ 5799/225 sx, MICT & CO, GRN Log,  
perf 5 way frac jet @ 5639 (Mor), 2" tbg set w/pkr @ 5628, swb  
NWO/Gas/3½ hrs, A/250 M + 27 BLO, MTP 2150# Vac, swb 1 hr &  
flo 27 BLW/1 hr, g 2,930 MCF/15 min & g 3,200 MCF/30" w/  
back press 110#, g 3,500 MCF/45 min w/back press 125#, g 4,200  
MCF/60" w/back press 160#, g 3,850 MCF/75" w/back press 140#,  
90" SITP 1660#, frac/2000 (3%) x Sd/2000#, MTP 4000-1800#, flow  
(2" tbg) g 5,592 MCF/30" w/125# back press, flow 7,972 MCF/  
2½ hrs w/130# back press, pull 2" tbg & pkr, set pkr @ 5634,  
perf 84/5608-29 (Mor sd), 2" tbg @ 5614, A/500 M @ 5608-29,  
MP 125 Bac/8", swb & flo LW + Gas, g 4,700 MCF, CP 520#,  
wtr-frac/10000 x 100000 gal 3% gel wtr, MCP 2200-1800/11 min,  
Reset tbg @ 5614, swb (2" tbg) 75 BLW/3 hrs, kicked off & flo  
4 hrs, gas g 9,780 MCF w/spray LW w/160# back press, CP 420#,  
R 125 BLW, 20 hr SICP 990#, 20 hr SITP 1560# from 5639 (Mor perf)  
flo thru 2½" tbg/2½ hrs, gas g 9,010 MCF/20 min, back press 180#,  
CP 910#, g 9,592 MCF/2½ hrs, BP 180#, CP 1080#, all w/heavy  
spray ld wtr. flowing to CO Hole, g 9,400 MCF/2 hrs w/heavy  
spray ld, CP 1520#, BP 170#, SI 2 hrs, g 9,592 MCF/2 hrs w/  
heavy spray ld, CP 1545#, Bp 170#, SI 18 hrs, g 9,592 MCF/  
2 hrs w/spray ld wtr & condnen, CP 1555#, BP 170#, g 9,592  
MCF/2 hrs w/spray ld wtr & cond., CP 1565#, BP 170#, CO 5671  
PBDT, CAOF 50,596 MCF, Morr 5608-39, FCP 1575, FTP 970,  
9/20/62.

AMARILLO ELECTRIC LOG TOPS

2554 DF

Winfield 2698 (-144)  
Heebner 4341 (-1787)  
Toronto 4364 (-1810)  
Lansing 4472 (-1918)  
Marmaton 5120 (-2566)  
Morrow 5594 (-3040)  
"S-2" 5607 (-3053) 22/27; IP 50,596 MCF  
Chester 5649 (-3095) DST/Mud  
RTD 5800