

3
 Singley Field
 Field ~~New Pool~~

State Kansas County Meade
 Company Gulf Oil Corp.
 Farm Shinogle "B" Well No. 1
 Sec. 20 Twp 33S Range 29W
 fr N fr E fr S fr W
 of NW SW

Contractor Garvey Tools

Remarks

Comm. 1-9-56 Comp. 2-29-56
 Elev. 2652 DF 26436 T. D. 5966 P. B.
 Pay 5780-5808

1 P. 11,300mg R. P. 1500 #

Casing Record: 13 3/8 ----- 7
 20 ----- 10 3/4 ----- 4 1/2 5964/200
 16 ----- 8 5/8 ----- 1511/900

	MIRT	Tops	SONG
		ANH 1420	
	9 7/8 @ 1511/900	Lay KL 4590	
		Murm 5255	
		Cik 5448	
		How Fog Tops	
		Lay KL 4594	
		Shatrol 5031	
	<u>5775-5825 - mur 46.6'</u>	Murm 5258	
	1' sh	Cik 5363	
	5.3' sd w sho o + g	Mur sh 5749	
	3.7' sd n.s.	Mur sd 5777	
	5' sd sho oil & gas - 15% upor.	Mur 5850	
	4.5' sd y sh.		
	5.1' sd. shale streaks bleed o.g.		
	3.5' shly sd - n.s.		
	5' sd. gd sho free oil est por 15-20%		
	2' l.m. - lite n.s.		
	11.6' sh thin streaks tile sd.		
	DS1 5780-5825 op 75"		
	975 in 6" g 163 MCF in 15"		
	189 mg in 1 hr - see 190' g cam.		

FP 140-200 BH 1880/20

DST 5852-5914 failed

DST 5863-5914 of 30" rec 30' mud FPO
BH 0/20

RTD 5966 ran log. running pipe

FEB 15 set 4 1/2" @ 5964/200 RUCT cot to 5909

of 112/5780-5808 A/500 m flush/96 bbb crude
subbed load set of 500 m of from 20,000
sd/30,000. FID 25 1/2 hrs. load & died.

51 hr. of wouldnt flow ran T to 5800 subbed 63
blbs load in 4 hrs to & flow 67 hrs load NW in 1 hr.

SIGM REP. SICP 1500#

FEB 22

BM. TEST

1st Test of 5,600 MCF 5 1/4" CK
CP 1200#

170-MEDIATE TEST 5,550 5 1/4" CK
CP 1171

FINAL TEST 3,000 MCF 1 1/4" CK
CP 1342#

FEB 29

- Cur of flow -
14,300 MCF.

~~CP~~ SICP 1500#

Ø