

WC

4

Field

State KansasCounty MeadeCompany Lion Oil Co. MONSANTO Chem. Co.Farm SingleyWell No. 1Sec. 20 Twp. 33SRange 29W

fr N fr E fr S fr W

of SE NEContractor Rhine Drlg.Remarks Aladdin FO Gulf DHM #12,500Comm. 9-2-55 Comp. 12-14-55Elev. 2678 T. D. 6010 P. B. 5550Pay 5803-11 5815-28 5892-5904I. P. Est 9,200 mcf S. I. T. P. 1650 #

Casing Record: 13 3/8 680/600 7  
 20 10 3/4 680/600 5 1/2 5949/300  
 16 8 5/8 2720/500

MIRT

Tops

Sample

SEP 7

1955

φ 2594

Hole 2650

SEP 14 1955

TTD 2781

Hole 2705

CG. 3193

DST 2915-23 1 hr. 110 4445nc 225' v sl. c sw Tot 4580FP 70-110 BH 620/30 Fury 4615φ 3940Mann 5245?

SEP 21 1955

DST 5055-69 upn 45 min Ck 5386etc. blo TO nc 80' m 1900' SWFP 560-1160 BH 1700/20 HH 2560φ 5400at 5555

SEP 28 1955

DST 5654-81 upn 30"nc 8' mud FPD BH 9/30DST 5755-5805 upn 1 hr. (Mud sd)GTS 10" g 400 mcf 25" 385 atind. of test nc 180' sl. g cmFP 105-105 BH 1635/30att DST 5800-15 pk failed.DST 5806-15 upn 2 hrs GTS 30"g 162 mcf in 40" g 390 mcf 90"g 370 in 2 hrs

MC 10' 9CM FPO-90 BH 1785/30  
RTO 6010 ran schl 6011

set 5 1/2 " 5949/300

M.I.C.T.

schl type

Kri 2783

OCT 5 1955 MICT CO 5911 Wurf 2834

ran GR log pf FTRil 2903

72/5892-5964 amb C.G. 3128

sls sho gas g 129mef Nb 4444

A/500m 12 hr gu 420mef KC 4486

frs/10,000 sd/10,000 Marn 5256

12 hr g - 2, 740mef Ck 5434

set plug 5871 pf 48/5803-11 Aten 5590

78/5815-28 g - 2, 740mef Mar 5777

A/1000m bla appr 1st Mar sd 5802-28

2800 mef wet w Acid 2nd " " 5890-5906

OCT 12 1955 APO: ran spinner muf test 5906

5824-28 fluid move - DM Plug c. 5850

treat 300 g gel X-80 A/250m frs/20,000

sd/20,000 A/5000 7.5% g 5,212 mcf

30 hrs. Apprx. + 1 1/2 Bp test fluid PH.

WOT

OCT 19 1955 ✓ 5777

OCT 26 1955 2678

FCP 200# SICP 1650 # SITP 1650#

blew for 6 hrs =

2 hrs 8,080 muf v. no mist from fluid

but 2 hr 7,560 muf " " "

FCP 680 #

SI

NOV 2 1955 26 hr BD g 2 010 muf. + 1/2 B of

fluid ph. FCP 640#

NOV 9 1955 SI BTU 1083

NOV 16 1955 SI

NOV 22 1955 1/2 BP TEST set 9,200 muf

held for press DEC 1 4 1955 absent

NOV 30 1955 DEC 7 1955