


State Kc. Field N.E. MAHLER
 Company SHAMROCK County MEADE
 Farm EDD ECKHOFF No. 2
 Sec. 26 Twp. 33 S Range 29 W

Spot SE SE NE
 Contractor D+M
 Remarks P.D. 5850



Comm. 7-12-58 Comp. 9-8-58
 Elev. DF 2457 GL KB TD 5785 PB 5723
 Pay Mar. 5686-5702

COE I.P. 5100 MCF + 17.1 B.O. + 40.1 BW/will.
 Press. SITP = 1610
SICP = 1601
 Casing Record: 13 3/8" 7"
 20" 10 3/4" 5 1/2" 5785/125
 16" 9 5/8 1535/750

spud, csg	Sample	Log
42155	Norwinger zone	HB-1817 4334
JUL 23 4496 1s+sh		5186 TORO-1907 4364
JUL 30 <u>5190-5213</u>	CHERO 5291	LAV-2035 4492
Rec 23' 1s	ATOKA 5389	MARM 5146
from well seal per	MoR 5610	Norwinger pay
blky wtr	Miss 5739	5218
DST <u>5192-5213</u>		Class 5322
Op. 1' full T.O.		ATOKA 5426
Rec 8'10" VSGCXW		MoR-3197 5654
(Cl 141,000 ppm)		Miss 5685-
SIP 1875/30"		-3228 5714
FP 55-400		CHES 5734
SIP 1575/30"		-3279
45496		
AUG 6 <u>5613-65</u>		
Rec 52' -		
40 1/2' 1s		
2 1/2' sh gan rather		
1' " tiny 3' ss tiny shly sta		
1' fl. blky oil		
1' 1s shly <u>gd bldg oil</u>		
2'4" ss shly " "		
1'8" 1s " "		

€ 5665-5716 REC. 50'-

1' ls drs; 3' sh sdy
3' " " 9' sh 1 1/2' ls
8 1/2" ss shly ~~fine~~, pow, str fl
bldg oil
3' ls ~~fine~~ = pow sh bldg or g
3' ss ~~shly~~ shly gd odors
6' " ~~fine~~ N.S.
8' " ~~gd~~ pow sh bldg or g
1' 4" ss N.S. 1' sh
1' 8" marl ~~gd~~ shly

DST 5685-5716 Op. 1' GTS-5"
8" g. 517 met, 15" - 1.1 T + stab.
REC. 105' GCM + 346' HO + GCM +
9' HO + GCM, SIP 1955/30", FP 150-330
SIP 1955/30"

€ 5716-49 Rec. 29' ls + sh - N.S.
RTD 5785 ls, S; 5786

~~WOC~~
AUG 13 CO. 5723

P/64 5686-5702, MIST
Ac 1000 ma, Swd, K.O., Rec. ld. +
8 BNO-11, 3/4" ck, g. 1024 MCF
FCP-365, Ac 500 (5%)
Ac frac 19 (5% gelac) x 10 rd
Ac 500 (5% oil) + 40 gals hi flow
flush w/ 1% ac wtr + 5" "
15" SIP 400, Swd 400 Bld-9'
K.O. flng ld + spray new oil, 3/4" ck
gas too wet to meas. ~~totg~~

AUG 20 22' flo 400 B. ~~pr~~ -
new oil + ld, 3/4" ~~thg~~ ck, g. 2310 met
STP-400, FCP-920, 24' SITP + CP-1600
~~ST~~

AUG 27 ~~WOT~~ SEP 3 g. 1150 MCF - 1 1/4" ck
CP-1340 TP-1060
Rec. 76 BNO + 92 BW-24'

~~totg~~
SEP 10 Swd ac. wtr + new oil
g. 1350 MCF

~~WOT~~
SEP 174 pl BPT 5100 MCF + 17.1 B.O. +
40.1 BW/inch (treat. wtr)?

SITP-1610, SICP-1601, RP-1929

Amarillo Tops -

Shamrock #2 Edd Eckhoff #2

2459 KB

Heebner 4327 (-1868)

Lansing 4492 (-2033)

Morrow 5673 (-3214) T 57', Tss 32'

"S-2" Sd 5683 (-3224) T 32', por

30', G 5,100 MCF / 17.1 BO /

40.1 BW/M

Chester 5736 (-3277) NT