


** *

State Ks Field W.C.
 Company SKELLY County MEADE
 Farm P.H. MOHLER No. 1
 Sec. 35 Twp. 33 Range 29

Spot SW SW SW

Contractor Hume

Remarks 6100 MISS SUNRAY DMM(4500)
T. EX. D.H.M.(5000)



Comm. 8-12-57 Comp. 10-23-57

Elev. DF 2495 GL 2487 KB TD 5906 PB 5228

Pay MARM 5259-67

I.P. St. Pat. 320 B&P D. Press. GRAV. 42°

Casing Record: 13 3/8" 7"
 20" 10 3/4" 5 1/2" 5906/300
 16" 8 5/8" 992/300

LOG	Sample	Log
<u>AUG 21 WOC</u>	<u>Heeb 4379</u>	<u>Heeb 4381</u>
<u>AUG 28 \$3170</u>	<u>LANS 4541</u>	<u>LANS 4541</u>
<u>SEP 4 \$4665</u>	<u>MARM 5181</u>	<u>MARM 5188</u>
<u>SEP 11 DST 5191-5204</u>	<u>CHER 5422</u>	<u>CHER 5418</u>
<u>op 1 hr. GTS 25"</u>	<u>MOR 5718</u>	<u>MOR 5714</u>
<u>TSTM rec. 135'</u>	<u>CHES 5802</u>	<u>CHES. 5802</u>
<u>MGC 800M EST</u>		
<u>10 to 25% oil + 90'</u>		
<u>MCSW + 360' GCSW</u>		
<u>FP 45-250 BHP 1650</u>		
<u>DST 5257-69 op 50"</u>		
<u>rec GTS 2 1/2" g 416 MCF/5"</u>		
<u>g 139 MCF/20" g 62 MCF/50"</u>		
<u>rec 325' oil GRAV 40 to 50°</u>		
<u>+ 245' MCOIL FP 150-245</u>		
<u>BHP 1240/20" \$5279</u>		

SEP 18 \$5741-78 rec. 26'; 4' sh good por
oil & stain & GAS, 1' congl., 1' sh, 2 1/2' sh
1' sh, 3' sh, 2 1/2' sh, 11' sh
DST 5741-78 op 1 hr. GTS 2" g 1,250 MCF
in 15" g 1,140 MCF/30" g 1,630 MCF/45"
g 1,710 MCF/1 hr. rec. 60' oil 90' GRAV 40
60' GCSW FP 150-230 BHP 1825
RTD 5906 ran log 5 1/2' DST (MISS) (OVER)

DST 5861-5906 op 1 hr rec, 50' M

~~FP~~ FP 75-95 BHP 945/30"

~~WOP~~

SEP 25 MICT CO 5884 G/R pt 54/5874-83

MA/500 swab 2BOPH + S.G. in 3 hr.

A/2000 swab 12BOPH + S.G. in 7 hr.

pl @ 5814 pf 18/5282-85 30/5294-99

MA/500 swab g 700MCF + 0.5. in 7 hr.

FR/6000 sd/6000 swab. load.

OCT 2 8 hr BD g 600MCF + OIL SHO

12 hr BD g 200 MCF + oil sho.

pl @ 5761 pf 48/5742-50 g 2,400MCF

+ 5BOPH/4hr. (16% wti) FR/2,000 sd/2,000

swab load 3 hr. BD g 3,669MCF + oil sho.

7 hr. SICP 1625 g 2,458MCF + 57.55 BOPH

16% wti FCP 190 pl @ 5278

pf 48/5259-67 (MARM) swab 8BO in 1 hr

MA/500 swab load swab 234 BO/16hr

est 15 BOPH 4% wti. ran T swab

170 BO/6hr.

~~SIWOT~~

OCT 9 ~~1~~ 3 OCT 16 Pump 8BO in 8 hr

OCT 23 comp 8hr. pump 106.79 BO + 4.44

B wti (grav. 42°) ST POT 320 BOPD

+ 12 BWPD

AMARILLO TOPS

2498 KB

Winfield 2726 (-228)

Heebner 4384 (-1886)

Lansing 4541 (-2043)

Marmaton 5188 (-2690) g 320 BOPD + 12 BWPD

Morrow 5714 (-3216)

"S-2" sd 5734 (-3236) T 20', por 12', tst'

2,500 MCF + 57.55 BO

in 7 hrs, plugged off

Chester 5802 (-3304)

TD 5906 (-3408)

94
60
3/768