


State K.S. Field Sampley
 Company Shamrock County Meade
 Farm Heinson No. 2
 Sec. 29 Twp. 33 Range 39

Spot 330 LNL, 1650 FEL

Contractor D. S. M.

Remarks _____



Comm. 2-10-57 Comp. 4-2-57

Elev. DF 2664^{25'} GL 2655 KB TD 5907 PB 5885

Pay 5856-74

I.P. 220.4 BOPD Press. 6137.5°

Casing Record: 13 $\frac{3}{8}$ 960/80 7" 5904/60

20" 103/4 5 $\frac{1}{2}$ "

16" 85/8

	Sample	Log
PUR	KC 4620	Shaw 4435
13 3/8	MOR 5803	Neck 4447
FEB 20	chester 5858	TDR 4486
Ø 3642		Lan 4619
FEB 27		Marin 5295
fish 4660		Cher 5464
MAR 6		AT 5572
rec fish, Ø 5372		MOR 5800
MAR 13		MS 5885
Ø 5815-60 rec 45' DST 5813-60, OP 75" Ø 64" TSTM, rec 110' hw 9cm, + 90' hw 0.9cm + 60' slim c o, + 30' oil, FP 35-75 BHP 1790/30		
reaming		
MAR 20		
Ø 5860-5907, rec 47' DST 5858-5907, OP 134, Ø 6", 8" 9 15BUCFI 15" 9 BB NEF rec 60' 9cm + 4800' oil, rec c line 100' slim c o + 76' 9cm + 100' hw ac w m, FP 240-1285, BHP 1920/30, RTD 5907, non log.		

~~7" Ø~~

over

CO 5885, PF 72/5856-74, ran T 5882

~~swelling~~

MAR 27

flo 190.80 in 26 hrs

st pot flo 220.4 BOPD (hrs 3/4" th

(937.5) CP 135

TP 25

gas 9 136 WCF

~~600 6 573~~

GOR 617-1

AMARILLO TOPS

2665 KB

Heebner 4468 (-1803)

Douglas 4476 (-1811)

Lansing 4620 (-1955)

Morrow 5800 (-3135)

"S-2" Sd 5842 (-3177) T 40', por 24', G 220 BOPD

TD 5902 (-3237)