

\* State Ks Field MOHLER EXT.  
 Company SKELLY County MEADE  
 Farm B. H. CORDES No. 1  
 Sec. 36 Twp. 33 Range 29

Spot N.W. N.W. N.W.

Contractor HULME

Remarks MISS



Comm. 1-1-58 Comp. 7-9-58

Elev. DF 2461. GL 2454. KB TD 5860 PB 5726

MOR  
Pay

5690-98 + 5704-09

ft/d I.P. 72 BOPD+42 BWPD+730 MCF  
 Press. than 2" to g.

Casing Record: 13 3/8" ..... 7"  
 20" ..... 10 3/4" ..... 5 1/2" 5860/250  
 16" ..... 8 5/8" 1457/1000

MTRT	Sample	Log
JAN 8 SPUD <del>φ 2455</del>	Heeb 4344	Heeb 4351
JAN 15 φ <del>3680</del>	LANS 4427	LANS <sup>3243</sup> 4504
JAN 22 φ <del>4765</del>	MARM 5148	MARM 5161
JAN 29 DST 5152-70	CHER 5386	CHER 5386
op lhr. rec. 1940' g	MOR 5669	MOR <sup>3209</sup> 5670
W D. Pipe +350' g 820	" sd 5690	" sd <sup>3329</sup> 5809
+50' M FP 20-185	<u>MISS 5756</u>	<u>CHESTER <del>5756</del></u>
BHP 1560/20"		<sup>-3282</sup> <u>5743</u>
DST 5192-5250		
op lhr. rec 40' M		
F 360' MSW FP		
20-210 BHP 1550/20"		
<del>φ 5430</del>		
FEB 5 φ 5694-5714		
rec 20'; 2' sh, 1' sd		
gd ord, 1 1/2' ls, 1' ls,		
5 1/2' sh, 1 1/2' ls, 2' sd oil sat, 5 1/2' sh		
DST 5691-5714 op lhr. GTS 3" g 580MCF/15"		
g 450MCF/1hr. rec 105' oil + 315 MCO +		
water. FP 70-180 BHP 1725/20"		
DST 5709-75 op lhr. rec 140' M FP 10-75		
BHP 1325/20" RTD 5360 run log		

FEB 12 DST 5778-5860 g/hr. rec. 100' M  
N.S. FP 20-60 BHP 200/200 ~~57g~~  
~~WGT~~

FEB 19 MICT, CO. 5846, GR, plus 5732  
PB 5724

P/20 5704-09  
30 5690-98, 1' B.D. 232 mcf  
filled w/ 200' oil, Ac 500 ma  
Swd 1 BNO PH, g 132 mcf then 5 1/2 - 7'  
SE 2.5 dies x 2, tbg 5722  
Swd + fluid 27 1/2 BNO + 13 BW - 15'  
then tbg, g 463 mcf, pull tbg  
tbg + pkr 5701, to til fr. 5704-09  
Swd w/TF (no oil) - 6', pull tbg + pkr  
C.O.

old log

after C.O. P/40 5844-54, Ac 500 ma  
Swd 300 gals x w/hr (N.S.) = 2 hrs

C.O. 5722, PB 5702 w/ seal ment

brail 4.8 BNO + 2.3 BW/hr - 8'

g. 53 mcf, C.O. 5712

Swd 1 B.fl/hr (60% oil + 30% wtr)

g. 80 mcf, C.O. 5726

P/5 5704-09

no-P/7 5690-98, Ac 500 ma

swd 2 B.fl/hr (60% oil + 30% wtr)

g. 310 mcf, SE mac 4 dips x 4 sd

~~FP-2000 Swd + fluid 1d~~

fluid 12 BNO + 7 BW - 10'

g. 730 mcf, S.T.

FTP-150  
ECP-450

MAR 5 48' SICP 1400

MAR 12 MAR 19 MAR 26 APR 1 APR 9

APR 16 APR 23 APR 30

MAY 7 MAY 14 MAY 21

MAY 27 JUN 4 JUN 11 JUN 18

JUN 25 JUL 2 JUL 9

← sale fluid 72 BOPD + 42 BWPD

2" tbg, g. 730 mcf

- WAIT. ON PIPELINE -

Meade County

36-33S-29W

Skelly #1 Cordes

NW NW NW

2463 KB

Heebner 4352 (-1889)

Lansing 4503 (-2040)

Morrow 5670 (-3207) T 87', 20' Tss

"S<sub>2</sub>" Sd 5690 (-3227) T 20', 14' por, G 72 BO / 92 BWPD

Miss 5757 (-3294)