


WC. 5

State Kansas Field Singley Pool
Company Texas Company County Meade
Farm Fox No. 1
Sec. 32 Twp. 33 Range 29

Spot C. SE. NE

Contractor Noble Drlg.

Remarks



Comm. 7/19/56 Comp. 8/29/56

Elev. DF 2590 GL 2581 KB TD 5894 PB

Pay 5810-18 5830-38

I.P. Flr. 47 BOPD Press.

Casing Record: 13 3/8 7" 5891

20" 10 3/4 5800/900 5 1/2"

16" 39 8 5/8

	Sample	Log
MIRT.	Kfi 2755	
JUL 18 <u>3100</u>	WINE 2790	
7/25 1 <u>4363</u>	UFTRIL 2840	
AUG 1 <u>5628</u>	L" " 2900	
JG 8 DST 5802-5851 op/ht.	Flot. 2950	
WK 580.55" <u>nc. 97' mud.</u>	WRE 3010	
FP 40 <u>775 BHP 145/20</u>	TOP 3916	
<u>5800-50</u> <u>nc. 36' (nodes)</u>	Nb 4401	- 4398
6' <u>l.m. lt. gray. fuky x l.m. sdy oil st.</u>	TOR 4444	4449
3' <u>sh.</u>	KC 4578	log. 4574
8' <u>ss. gr. f. q. seat. gd oil strain</u>	MAMM 5230	5244
13' <u>bl. carb. sh.</u>	ATOKA 5588	CR 5435
1' <u>l.m. fuky x l.m. qty. buff</u>		ATOKA 5586
4' <u>sh. bl. carb.</u>		Mot 5762
6' <u>l.m. qty. fuky x l.m. sdy sli gluc. sli stain.</u>		55 5809-17
<u>5851-5885</u> <u>nc. 28' (No dis)</u>		55 5830-38
11' <u>lost.</u>		Miss 5863
2' <u>lt. gray. ss. v. f. q. shly w sli flow.</u>		
5' <u>l.m. den. gray.</u>		
7' <u>l.m. f. to med x l.m. shly in part.</u>		
5' <u>l.m. buff. med x l.m. sli sdy.</u>		
4' <u>l.m. buff. to brn.</u>		
RTD 5894 <u>same log set 7" @ 5891</u>		

AUG 15 EVCT cost? ^{pp} 32/5830-38 32/5810-18
A/Soom from 10,000 oil ad/15,000# flowed 82 bbls
load in 4 hrs thr 1/2" ck. + died. scrubbed 28.4
bbls load in 12 hrs - gd sh of gas. scrubbed
17 bbls load + 214 bbls new oil in 22 hrs
51 for tanks.

Aug. 22 flow 36 B0, no wtr / 4 hr (1/4" ch)
TP 175#, flow 24 B0, no ~~2~~ wtr / 4 hr (1/2" ch)
flow 40 B0, no wtr / 5 hr (1/4" ch) TP 150#

AUG 29 ^{5890 TD}
Completion gauge
PBTO F10 31 BOPD 5% wat 12/64 ck.
GOR 768:1
qt 38.7.
Allowable ~~NA~~ 47 BOPD 5810-
^{pp 5830-38}
⁵⁸¹⁰⁻¹⁸
A1 47 BOPD

AMARILLO TOPS

2591 KB

- Winfield 2789 (-198)
- Heebner 4422 (-1831)
- Lansing 4580 (-1989)
- Marmaton 5246 (-2655)
- Morrow 5762 (-3168)
- Morrow Sd 5809 (-3239) T 6', por 6', G 47 BOPD + 5% XW
- Morrow Sd 5830 (-3339) T 8', por 8'
- Chester 5863 (-3272)
- TD 5894 (-3303)