

MAP NO. _____ ELEV. 2677 DF
 STATE Kansas COUNTY Meade SEC. 31 Twp 33 S Rge 29 W
 OPERATOR Thomas & Brewer - Liberal, Kansas LOC. C SW SE
 WELL NO. 1-31 FARM NAME H. G. Adams FT. FROM _____ LINE _____
 POOL Novinger, E FT. FROM _____ LINE _____
 FR. 12-2-60 SPUD 11-30-60 COMP. 3-5-61

CONT./GEOL. Bennett & Roberts

COMPLETION RECORD
 NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
 a Morrow 5834-5900 56 2000Ac-AF/40X40

b _____

c _____

d _____

a I. P. OIL/DIST. WTR. COF GAS 5,400 M.C.F.P.D. CHK. 4 pt HRS. _____

b " " (no fluid est) " " " "

c " " " " " "

d _____

SITP 1564

SICP 1419

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 5912 TD 6000

SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.

8-5/8" 625 625 _____ _____ _____

4 1/2" 5960 125 _____ _____ _____

OPERATOR Thomas & Brewer WELL NO. 1-31 H.G. Adams ELEV. 2677 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Toronto	4570	-1893			
Lansing-Kansas City	4646				
Morrow	5817	-3140			
Morrow Sand	5831	-3154			
Morrow Sand	5885	-3208			
Chester	5963	-3286			

Spud 11-30-60. 8-5/8" @ 625 w/625 sx.

DST # 1 (Morr) 5790-5890, op 1 hr, gd blo, rec 115' GCM, FP 42-210, SIP 548/30 mins.

DST # 2 (Morr) 5893-5960, op 1 hr, GTS 43 mins/TSTM, rec 195' GCM + 270' HOCM, FP 63-105, SIP 1632/30 mins.

TD 6000, logs. 4 1/2" @ 5960 w/125 sx. MICT, CO to 5912.

P/4/5834-35, 4/5847-48, 4/5855-56, 4/5873-74, 40/5890-5900.

2000-15% MA. Rec 1d. Flod 1 1/2 BO + 150 MCF. Frac 40,000

Ac X 40,000 sd. Rec 1d. Ga 9,000 MCF + 30 BOPD. Set 2"

tbgs @ 5903.

IP 4 pt COF 5,400 MCF (no fluid est), SITP 1564, SICP 1419, from Morrow (5834-74)

COMPLETE 3-5-61

2679BF

Liberal Tops

Sheeh	4500	-1823	
Saus	4656	-1979	
Marm	5310	-2633	
mor	5817	-3140	bet 115' Gcm & 5.4M
S ₂	5884	-3207	bet Gcm + HOCm
miss	5970	-3293	
TD	6000		