

Disc Arkalon West

9-275W
 STATE Kans MAP NO. 84
 COUNTY Seward SEC. 29-33S-32W
 OPER Cities Service Oil Co. - Liberal, Kansas LOC. C NE SW
 WELL I FARM Salley "D" FT/FR LINE
 Wildcat FT/FR LINE
 Lohmann-Johnson ELEV. 2652 GR. 2661 DF 2663 KB
 CONT. 6250' Miss Test GEOL. Dean Hines
 F.R. 7-25-63 SPUD 7-25-63 COMP. 9-24-63
 TD 6425 FM. St Louis PBT. 5884
 PRODUCING FM. FROM TO PERF W/HOLES TREATMENT
 Morr sd 5694-5748 124 4000A & Frac
 I.P. COF: 50,000,000 Cfgpd (SITP 1558#)
 WC-3 miles N of Lans O&G & Mor G in Condit Field
 8" @1461 w/425 sx. 4 1/2" @5910 w/100 sx.

Data Inc.

(KB Spl)			(KB Log)		
Hb	4190		Winf	2602	+ 61
Tor	4220		CG	2878	- 215
Lans	4350		Hb	4190	-1527
Marm	5010		Tor	4210	-1547
Morr	5546		Lan	4352	-1689
RTD	6425	-3762	Marm	5010	-2347
			Morr	5553	-2890 (Cont)

DST #1 (CG) 3351-3400, Op 1 hr, Morr sd 5692
 R 730' SGCSW, IFP 55#, FFP 381#, FSIP 890#/30" 5748 -2930
 Chest 5748 -3085
 DST #2 (Lan) 4505-55, Op 1 hr, St Gen 6088 -3425
 R 90' Mdy SW + 875' SW, St Lou 6164 -3501
 IFP 139#, FFP 638#, FSIP 1357#/30" LTD NA
 DST #3 (Mor) 5700-35, Op 1 hr, GTS/3", Ga 1,200,000 Cfgpd/NT,
 Ga 2,550,000 Cfgpd/60", R 95' HGCM, ISIP 1915#/20", IFP
 487#, FFP 571#, FSIP 1841#/20", RTD 6425, Sj Log, 4 1/2"
 @5910 w/100 sx., CO 5885, 48/5736-48 (Mor sd), Ga 312,000
 Cfgpd + 5 BLWPH/3 hrs, 500A, Ga 1,750,000 Cfgpd, dry/21 hr test,
 PB 5730, 24/5714-20 (Morr), Ga 1,940,000 Cfgpd, dry/12 hrs, CO
 5884, Ga 2,210,000 Cfgpd/8 hr test, PB 5710, 56/5694-5708 (Mor),
 Ga 1,208,000 Cfgpd/4 hrs, 500A, Ga 3,040,000 Cfgpd + 2 GAW/10
 hrs, 3000A (15%), Ga 4,520,000 Cfgpd + tr wtr + 2 bbls dist/1
 hr in 35 hrs, CO 5884 PBT, Ga 2,102,000 Cfgpd + 30 gal LWPH/
 12 hrs, Ga 3,020,000 Cfgpd + 30 gal W & dist PH/21 hrs, Frac
20,000 G gell W x 20,000# sd + 55 ball sealers in perfs 5694-
5748, Ga 23,100,000 Cfgpd (surging dist)/21 hrs, Ga 4,500,000
Cfgpd + 978 G dist + 52 1/2 GW/17 hrs, Sep Pr 525#, Ran 1 1/2" tbg to
5691, Cal OF 50,000,000 Cfgpd-dry, SITP 1558# from Mor sd perfs
5694-5748 - WT - WO Conn - COMPLETED

2663 KB

Lower Krider 2540 (+123) Winfield 2602 (+61)

Council Grove 2878

Heebner 4190 (-1527)

Toronto 4210 (-1547)

Lansing 4352 (-1689)

Marmaton 5010 (-2347)

Morrow 5553 (-2890)

"S-2" Sand 5692 (-3029) 40/56; ϕ 50,000 MCF


Chester 5748 (-3085)

Ste. Gen 6088 (-3425)

St. Louis 6164 (-3501)

TD 6425

9-275W
 MAP NO. Seward
 COUNTY Liberal, Kansas
 CITY Salley "D"
 WELL Wildcat
 POOL Lohmann-Johnson
 CONT. 6250' Miss Test
 7-25-63 SPUD 7-25-63
 F.R. 6425 FM. St Louis
 TD 6425
 ELEV. 2652 GR. 2661
 GEOL. Dean Hines
 COMP. 9-24-63
 P.B.T.D. 5884
 PERFORMANCES
 TREATMENT



PRODUCING FM. FROM TO
 Morr sd 5694-5748 124 4000A & Frac
 COF: 50,000,000 Cfgpd (SITP 1558#)
 WC-3 miles N of Lans O&G & Mor G in Condit Field
 8" @1461 w/425 sx. 4 1/2" @5910 w/100 sx.

Data Inc.

(KB Spl)		(KB Log)	
Hb	4190	Winf	2602 + 61
Tor	4220	CG	2878 - 215
Lans	4350	Hb	4190 -1527
Marm	5010	Tor	4210 -1547
Morr	5546	Lan	4352 -1689
RTD	6425 -3762	Marm	5010 -2347
		Morr	5553 -2890 (Cont)

DST #1 (CG) 3351-3400, Op 1 hr, Morr sd 5692 -2930
 R 730' SGCSW, IFP 55#, FFP 5748 -3085
 381#, FSIP 890#/30" Chest 5748 -3425
 DST #2 (Lan) 4505-55, Op 1 hr, St Gen 6088 -3501
 R 90' Mdy SW + 875' SW, St Lou 6164
 IFP 139#, FFP 638#, FSIP LTD NA
 1357#/30"
 DST #3 (Mor) 5700-35, Op 1 hr, GTS/3", Ga 1,200,000 Cfgpd/NT,
 Ga 2,550,000 Cfgpd/60", R 95' HGCM, ISIP 1915#/20", IFP
 487#, FFP 571#, FSIP 1841#/20", RTD 6425, Sj Log, 4 1/2"
 @5910 w/100 sx., CO 5885, 48/5736-48 (Mor sd), Ga 312,000
 Cfgpd + 5 BLWPH/3 hrs, 500A, Ga 1,750,000 Cfgpd, dry/21 hr test,
 PB 5730, 24/5714-20 (Morr), Ga 1,940,000 Cfgpd, dry/12 hrs, CO
 5884, Ga 2,210,000 Cfgpd/8 hr test, PB 5710, 56/5694-5708 (Mor),
 Ga 1,208,000 Cfgpd/4 hrs, 500A, Ga 3,040,000 Cfgpd + 2 GAW/10
 hrs, 3000A (15%), Ga 4,520,000 Cfgpd + tr wtr + 2 bbls dist/1
 hr in 35 hrs, CO 5884 P.B.T.D., Ga 2,102,000 Cfgpd + 30 gal LWPH/
 12 hrs, Ga 3,020,000 Cfgpd + 30 gal W & dist PH/21 hrs, Frac
 20,000 G gell W x 20,000# sd + 55 ball sealers in perfs 5694-
 5748, Ga 23,100,000 Cfgpd (surging dist)/21 hrs, Ga 4,500,000
 Cfgpd + 978 G dist + 52 1/2 GW/17 hrs, Sep Pr 525#, Ran 1 1/2" tbg to
 5691, Cal OF 50,000,000 Cfgpd-dry, SITP 1558# from Mor sd perfs
 5694-5748 - WI - WO Conn - COMPLETED