

Incl
State Geological Survey
WICHITA BRANCH

21
5-33-3W

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Baker #1
C-E/2-NW-SE Sec 5-33S-3W
Sumner County Kansas

Commenced: 7-2-78

Completed: 7-13-78

OPERATOR: ROCKWOOD PETROLEUM CO.

Depth From	to	Formation	Remarks
0	100	Redbed-Shale	Ran 6 jts of 28# 8 5/8" csg
100	257	Shale-Shells	set @ 254' Cemented w/200 sks
257	350	Redbed-Shale	Common 2% CC
350	852	Shale	PD @ 8:00 P.M. 7-2-78
852	1090	Shale-Shells	
1090	1224	Shale-Lime	
1224	1520	Shale-Shells	
1520	1770	Shale-Lime	Ran 98 jts of 14# 5 1/2" csg
1770	2995	Shale	set @ 4035' Cemented w/
2995	3015	Shale-Sand	150 sks 60/40 Posmix 10% Salt
3015	3105	Sand-Shale	7# Gilsonite per sack
3105	3230	Shale	250 gallons Mud Flush
3230	3365	Shale-Lime	PD @ 12:20 p.m. 7-13-78
3365	3485	Lime-Shale	
3485	4035	Lime	
	4035 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 18th day of July, 1978.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.