

5-33-3W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- BEARDMORE & O. A. SUTTON
Farm- Mühlenbruch No. 1

SEC. 5 T. 33 R. 3W
NW NW SE

Total Depth. 3420'
Comm. 5-16-54 Comp. 5-25-54
Shot or Treated.
Contractor. Beardmore Drilling Co.
Issued. 7-31-54

County Sumner
KANSAS



CASING:
8 5/8" 214' cem w/100 sx
5 1/2" 3413' cem w/60 sx

Elevation. 1217' DE

Production. 63 BO & 15% wtr.

Figures Indicate Bottom of Formations.

cellar	5
S. soil	35
red rock - shale	214
shale - shells	610
lime broken	845
lime	1060
lime - shale	1460
shale - lime	2120
lime - shale	3000
lime	3115
lime - shale	3220
lime broken	3300
cored	3310
lime	3420
Total Depth	

Tops:
Lansing 3294

DRILL STEM TESTS:

#1 3307-3313, open 1 hr., shut in 30 min.
rec. 30' mud. BHP 530#.

#2 3365-3394, Rec. 30' oil cut mud, 60'
gas cut mud, 60' muddy oily water,
360' water. Open 1 hr., shut in 15
min. BHP none IF Zero FFP 260#.

#3 3415-3423, open 1 hr., shut in 15 min.
gas to the surface in 12 min. Rec.
460' gassy muddy oil. 30' water.
BHP 1200#. IF 100#. FF 160#.