

5-33-3W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE & SUTTON
Farm- Pearce No. 1

SEC. 5 T. 33 R. 3W
SE SW NE

Total Depth. 3435
Comm. 7-6-54 Comp. 7-11-54
Shot or Treated.
Contractor. Beardmore Drlg. Co.
Issued. 8-7-54

County Sumner
KANSAS



CASING:

8 5/8" 157' com. w/90 sx

Elevation. 1212 DF

Production. dry

Figures indicate Bottom of Formations.

cellar	5
redrock	90
sand	120
redrock, shale & shells	157
shale & shells	500
lime broken	760
shale & lime	3315
lime	3435
Total depth	

Tops:
Topeka Lime 2765
Stalnaker sand 3010
Kansas City lime 3307

DST #1 3311-30: Open 1 hour, light
blow thruout, recovered 270' muddy
salt water. 1400# B.H.P.

DST #2 3378-89: Open 1 hour, light
blow thruout, recovered 180' muddy
water, specks of oil. 1440# B.H.P.

DST #3 3428-35: Open 1 hour, fair
blow thruout, recovered 135' salt
water. 1360# B.H.P.