

PI

TYPE

SIDE ONE

CONFIDENTIAL

18-33-3W

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5146 EXPIRATION DATE

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-191-21,509

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Sumner  
Wichita, Kansas 67202 FIELD

\*\* CONTACT PERSON Juanita Green PROD. FORMATION  
PHONE 265-9686

PURCHASER LEASE Frazier

ADDRESS WELL NO. #2

WELL LOCATION SW SW SE

DRILLING Rains & Williamson Oil Co., Inc. 330 Ft. from South Line and

CONTRACTOR CONTRACTOR ADDRESS 435 Page Court, 220 W. Douglas 2310 Ft. from East Line of

Wichita, Kansas 67202 the (Qtr.) SEC 18 TWP 33S RGE 3 (W).

PLUGGING Same WELL PLAT (Office Use Only)

CONTRACTOR CONTRACTOR ADDRESS

ADDRESS

TOTAL DEPTH 4550' PBTD

SPUD DATE 1-15-83 DATE COMPLETED 1-30-83

ELEV: GR 1248 DF KB 1257

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 525' DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


KCC  
KGS  
SWD/REP  
PLG.

A F F I D A V I T

Wilson Rains, President

that: being of lawful age hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Wilson Rains

RELEASED FEB 1 1984

PL

OPERATOR Rains & Williamson Oil Co., Inc. Frazier #2

FILL IN WELL INFORMATION AS REQUIRED: WELL NO.

Show all important zones of porosity and contents thereof; cased intervals, and oil drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
DST #1 - 3647-3661, 30 (30) 90 (60). Rec. 835' GIP, 35' GCM, 30' HG&OCM. IFP's 42-42. IBHP 232, FBHP 975.			<u>E. LOG TOPS</u>	
DST #2 - 4096-4104, 30 (30) 60 (60). Rec. 90' WM, 60' SI.OCMW, 120' V.SI. OCMW. FP's 80-80, 80-80. IBHP 1580, FBHP 1580.			Iatan	3068 (-1811)
DST #3 - 4490-4502, 30 (30) 30 (30). Rec. 35' SI. Oil specked mud. FP's 20-20, 20-40. IBHP 30, FBHP 40.			Kansas City	3409 (-2152)
DST #4 - 4494-4508, 30 (30) 30 (30). Rec. 10' mud. FP's 30-30, 50-50. IBHP 50, FBHP 50.			Stark Shale	3566 (-2309)
DST #5 - 4508-4523, 30 (30) 60 (30). Rec. 120' mud. FP's 50-50, 70-95. IBHP 1465, FBHP 1310.			Cherokee Sh.	3934 (-2677)
			Miss. Chert	4087 (-2830)
			Kinderhook Sh	4420 (-3163)
			Simpson Sd.	4494 (-3237)
			LTD	4546 (-3289)

If additional space is needed use Page 2, Side 2

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	525'	Common	275 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

PI

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 18 T. 33S R. 3W

WELL NAME: Frazier #2

LOC. SW SW SE

COUNTY: Sumner

RIG NO. #3

TOTAL DEPTH 4550'

ELEVATION 1248 GL 1257 KB

COMMENCED: 1-15-83

COMPLETED: 1-30-83

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 525' w/275 sx. common, 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	1911
Shale & Lime	2455
Lime & Shale	2635
Shale & Lime	2810
Lime & Shale	3175
Lime	4550
<u>ROTARY TOTAL DEPTH</u>	<u>4550</u>

MAR 7 1983

State Geological Survey  
WICHITA BRANCH

STATE OF Kansas )

COUNTY OF Sedgwick )

SS:

Wilson Rains, President

of Rains & Williamson Oil Co., Inc.