

State Geological Survey
WICHITA BRANCH

15-191-20630

22-33S 3W

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Rohrer #1
150' W of SE SE SE Sec 22-33S-3W
Summer County Kansas

Commenced: 11-16-76

Completed: 11-30-76

OPERATOR: ALLISON OIL CO.

Depth		Formation	Remarks
From	to		
0	256	Redbed	Ran 6 jts of 8 5/8" csg set @ 253' Cemented w/ 225 sks - 2% Gel - 3% CC PD @ 8:45 p.m. 11-16-76
256	650	Shale	
650	1192	Shale-Shells	
1192	1360	Lime-Shale	
1360	1630	Shale	
1630	1865	Shale-Lime	Ran 86 jts of New 4 1/2" csg set @ 3596' Cemented w/100 sks 50/50 posmix 18% Salt - 3/4 of 1% CFR-2 PD @ 2:15 a.m. 11-30-76
1865	2020	Lime-Shale	
2020	2200	Shale	
2200	2600	Lime-Shale	
2600	2810	Shale-Lime	
2810	3035	Lime-Shale	
3035	3115	Sand	
3115	3145	Shale-Lime	
3145	3275	Shale-Sandy Lime	
3275	3820	Lime	
3820	3885	Lime-Shale	
3885	4430	Lime	
4430	4475	Shale	
4475	4481	Lime	
	4481 - TD		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me this 6th day of December, 1976.