


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHAMROCK OIL & GAS CO.
 Farm- Langhofer No. 1

SEC. 18 T. 33 R. 30W
 NW NW SE

Total Depth. 5698' PB 5690'
 Comm. 6-21-55 Comp. 8-25-55
 Shot or Treated.
 Contractor.
 Issued. 10-12-57

County Meade
 KANSAS



Elevation. 2732 (magnolia sent report)
 Production. 9,000,000 CFGPD

CASING:

13 3/8" 638' w/500 sx cem.
 9 5/8" 2630' w/800 sx cem.
 5 1/2" 5693' w/300 sx cem.

Figures indicate Bottom of Formations.

clay-sand	126
red rock-sand	700
red rock-sand-salt	1180
red rock-gyp-shells	1633
red rock-gyp-shale	1809
gyp-shale	1969
red rock-gyp	2000
gyp-shale	2261
gyp-shale-anhydrite	2312
gyp-shale-anhydrite	2380
gyp-anhydrite	2438
anhydrite	2483
gyp-anhydrite	2491
anhydrite	2602
lime-anhydrite	2641
lime-shale	2702
lime-dolomite	2912
lime-dolomite-sand	2977
lime-shale	3360
lime	3428
lime-shale	4054
lime-shale	4688
lime	4752
lime-shale	4990
lime-shale	5615
Coring	5662
shale-anhydrite -lime	5693 RTD
No record	5698
Total Depth PB 5690	

TOPS:

Shawnee	4304
Lansing	4483
Marmaton	5108
Cherokee	5275
Atoka	5391
Morrow	5608
Chester	5663