


11-83W
 MAP NO. _____
 STATE Kans COUNTY Seward SEC 30 TWP. 33S RGE 31W
 OPERATOR Whitehall Oil Co., Inc., Dallas, Tex. LOC C NE SW
 WELL NO. 1 FARM NAME Rice Davies
 POOL Wildcat FT. FROM _____
8/14/62 SPUD 8/27/62 DEPTH 2565 PS FT. FROM _____
 OR 2578 DP 2581 KA
 CONT. P. S. & B. Drlg. Co. COMP 11/6/62

NAME PRODUCING INTERVAL (corr) Morr COMPLETION RECORD / GEOLOGICAL
 FROM - TO 564-585654-68 PERM. W/ HOLES 56 TREATMENT RECORD
500 A
Cal OF 6,789 MCF (corr) 16,800 16,800 GAS M.C.F.P.D. _____ CHK. _____ WRS. 24



SPR 1610# FI TP # _____ FI CPH _____ SIDHP _____ D & A ()
 GOR _____ GR. _____ TD 6174
 SIZE DEPTH CASING - CEMENT RECORD SIZE DEPTH W/SAX.
16" @ 75 6 yards 4 1/2" @ 5792 200
8 5/8" @ 2346 850

OPERATOR Whitehall Oil WELL NO. 1 Rice Davies ELPY 2565 GR

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
RTD (St L)	6174	-3609	GR Tops & Datums		
RTD 6174. Log.			Herr	2449	+ 116
WLT #1 (L/Morr) 5663-65 1/2			Kri	2481	+ 84
Op 90", R .15 CFG+1200			Winf	2578	- 13
CC filt wtr, IBHP 1900#/ 44", FBHP 150#/11"			CG	2851	- 286
DST #1 (StL) 6152-74, Op 1 hr., R 60' M, IBHP 2084#/30", IFP 76#, FFP 86#, FBHP 896#/15".			Tor	4490	-1925
4 1/2" @ 5792 w/200 sx. Log.			Marm	5006	-2441
Perf 56/5654-68 (Morr), 500 A, St. Gen			Chero	5165	-2600
Ga 400 MCFGPD, Frac(20,000 gal + 12,000# sd), SI 48 hrs., 20" BD, Ga 4,924 MCFGPD, Cal OF 16,800 MCFGPD, SITP 1610#.			Morr	5538	-2973
Morr 5654-68, 10/25/62.			LoMorr sd	5651-70	-3086
5644-58 (corr)			Miss	5676	-3111
			St. Gen	5988	-3423
			St. Lou	6110	-3545

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2580 KB

- Winfield 2576 (+4)
- Council Grove 2808 (-228)
- Heebner 4168 (-1588)
- Toronto 4188 (-1608)
- Lansing 4316 (-1736)
- Marmaton 5006 (-2426)
- Morrow 5338 (-2958)
- "S-2" 5651 (-3071) 16/18; ϕ 16,800 MCF
- Chester 5688 (-3108)
- Ste. Gen 5988 (-3408)
- St. Louis 6078 (-3498) tst mud
- TD 6174

5338
4168
2958

1712