

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20272-00-00

LEASE NAME Graber

WELL NUMBER 3

4950 Ft. from S/W Line of Section (circle one)

4450 Ft. from E/W Line of Section (circle one)

SPOT LOCATION - - - - - NW - NW

SEC. 7 TWP. 33 S. RGE 31 (E) or (W)

COUNTY Seward

Date Well Completed 11/17/75

Date Plugging Commenced 2/28/02

Date Plugging Completed 3/5/02

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468

CITY, STATE, ZIP Tulsa OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Gas
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 2/28/02 (date)

by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? On old form not, is well log attached? n/a

Producing Formation(s) Toronto Depth to Top 4247 Bottom 4283 T.D. 4424

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Toronto	Gas	4247	4283	8 5/8	1539	-0-
				5 1/2	4374	2431

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4200' w/2 sxs cmt on top to 4180'. Located free-point & cut off 5 1/2" casing @ 2431'.
POOH & LD. Circ'd hole w/ mud. Pumped 50 sx cmt plug from 1570'-1420'. Pumped 40 sx cmt plug
from 600'-480'. Pumped 10 sx cmt plug from 40'-surface. Cut off & capped 8 5/8" casing 3'
below G.L. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc.

License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN to before me this 11 day of March, 19 2002



OFFICIAL SEAL
WYNONA YATES
Tulsa County

Notary Public

My Commission Expires: 11/16/2003

RECEIVED

APR 01 2002

KCC WICHITA

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20272-00-00

Spot: W2NENWNW

Sec/Twnshp/Rge: 7-33S-31W

330 feet from N Section Line, 830 feet from W Section Line

Lease/Unit Name: GRABER

Well Number: 3

County: SEWARD

Total Vertical Depth: 4424 feet

Operator License No.: 6568

Op Name: KAISER-FRANCIS OIL COMPANY

Address: PO BOX 21468
TULSA, OK 74121

Conductor Pipe: Size feet: 8 1/43.78

Surface Casing: Size 8.625 feet: 1539 WITH 250 SX CMT

Production: Size 5.5 feet: 4374 WITH 150 SX CMT

Liner: Size feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/05/2002 10:30 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Revd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: LOAD HOLE WITH MUD. SET CIBP @ 4200' WITH 2 SX CMT. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/05/2002 5:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4375'. PERFS AT 4247-83'. CIBP @ 4200' WITH 2 SX CMT. LOADED HOLE & PRESSURED 5 1/2" TO 700'. HELD. 1ST PLUG PULLED OUT OF HOLE TO 1570'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH CASING TO 600'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT.

RECEIVED
MAR 11 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

MAR 07 2002

DATE Mar 12, 02

INV. NO. 2002061509

Form CP-2/3
MP