

TYPE

AFFIDAVIT OF COMPLETION FORM*

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6230EXPIRATION DATE 6/30/84OPERATOR First National Oil, Inc.API NO. 17520,550ADDRESS 23 East 11th St.COUNTY SewardLiberal, KS 67901

FIELD _____

** CONTACT PERSON Montgomery A. EscuePROD. FORMATION MorrowPHONE (316) 624-1664PURCHASER PetrosourceLEASE Diamond-SleeperADDRESS 7290 Samual Drive - Suite 103WELL NO. 1Denver CO 80221WELL LOCATION Nw/4 Se/4DRILLING Midco Drilling, Inc.1980 Ft. from South Line and

CONTRACTOR

ADDRESS 200 East First, Suite 5202310 Ft. from East Line ofWichita, KS 67202the Se (Qtr.) SEC 25 TWP 33 SRGE 31 W.PLUGGING N/A

WELL PLAT

(Office
Use Only)

CONTRACTOR

ADDRESS _____

KCC
KGS ☒SWD/REP
PLG. _____TOTAL DEPTH 8350' PBDT 6109'SPUD DATE 10/15/81 DATE COMPLETED 4/29/82ELEV: GR 2722' DF 2736' KB 2737

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE N/AAmount of surface pipe set and cemented 1697' KB DV Tool Used? NoneTHIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Montgomery A. Escue, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

OPERATOR First National Oil, Inc. LEASE Diamond-Sleeper SEC. 25 TWP. 33S RGE. 31W

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Bridge Plug set at 6110' (Cast Iron) w/2 sx cement DST #1 IF 30"; ISI 61"; FF 60"; FSI 118"; IH 3901#; IFP 85-342#; ISIP 2883#; FFP 421-674"; FSIP 2890#; FH 3767# @155 degrees Rec. 130' drlg mud 1400' Saltwater	8233	8294		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 - 20-40 sand; 30,000 gals. 70% foam - nitrogen flush	5676-84 - 5648-566
Date of first production September, 1984	Producing method (flowing, pumping, gas lift, etc.) Pumping
Estimated Production -I.P. Oil 6/week bbl-r.	Gravity
Gas 1120 MCF	Water % bbls
Disposition of gas (vented, used on lease or sold)	Gas-oil ratio CFPB
Shut in	Perforations 5676-84 5648-5660

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	17 1/2"	13 3/8	J-55 54.5	1697	Howco Lite Class H	1500 200	
Intermediate	13"	9 5/8"	K-55 40#	6117	Howco Lite	250 300	
Production		5 1/2"	14#	5570	50/50 Poz	100	10% salt 3/4 of 1% CF

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4 SPF		5676-84

TUBING RECORD

Size	Setting depth	Packer set at
2 7/8"	5680	

Shots per ft.	Size & type	Depth interval
4 SPF		5648-5660