


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **PANHANDLE DEVELOPMENT CO., INC.**
 Farm- **Simonson** No. **4**

SEC. **27** T. **33** R. **31W**
 C SW SE

Total Depth. **5920'**
 Comm. **1-19-62** Comp. **2-9-62**
 Shot or Treated.
 Contractor. **McClellan Drlg.**
 Issued. **6-30-62**

County **Seward**
KANSAS



Elevation. **2733'** RB

Production. **383 BOPD**, Tr. Wtr.

CASING:

8 5/8" 1248.85' cem w/650 sx.
5 1/2" 5909' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay & sand	250
sand & gyp	640
red bed & sand	1010
sand	1050
red bed & sand	1110
red bed & gyp	1265
red bed & Anhydrite	1550
Anhydrite & shale	1950
shale & Anhydrite streaks.	2100
Anhydrite & shale	2300
shale & lime	2425
lime	3120
shale & lime	3255
lime	3685
lime & shale	3790
lime	3850
lime & shale	4220
lime	4290
lime & shale	4300
lime	4520
lime & shale	4620
lime & shale	4620
lime	5920 BOPD
Total Depth	

TOPS: SCOUT

Council Grove	3063
Heebner	4239
Toronto	4276
Lansing	4396
Kansas City	4401
Marmaton	5048
Cherokee	5207
Morrow	5527
St. Genevieve	5677