

DRILL STEM TESTS

DST #1 from 2665' to 2745', open 1 hour, weak blow, increasing to fair after 5 minutes, recovered 15' gas cut mud.

Pressures:

IFP. 50#
FFP. 300#
BHP (20 min) 575#

DST #2 from 4492' to 4512', open 1 hour, fair blow, recovered 750' SW.

Pressures:

IFP. 50#
FFP. 350#
BHSIP (15 min.) 1225#

DST #3 from 4678' to 4694', open 1 hour, weak blow, increasing slightly throughout test, recovered 190' sl/gas cut salty DM.

Pressures:

IFP. 0#
FFP. 0#
BHSIP (20 min.) 1100#

DST #4 from 4949' to 4972', open 1½ hours, fair blow throughout test, recovered 585' muddy SW.

Pressures:

IFP. 25#
FFP. 350#
BHSIP (20 min.) 1650#

DST #5 from 5183' to 5198', open 1 hour, fair blow, increasing throughout test, recovered 480' muddy SW.

Pressures:

IFP. 25#
FFP. 275#
BHSIP (20 min.) 1600#

DST #6 from 5557' to 5607', open 2 hours, strong blow, gas in 10 minutes, recovered 360' gas & sl/OCDM, trace free oil in testers tool.

Pressures:

IFP. 125#
FFP. 200#
BHSIP (20 min) 1800#

DST #7 from 5575' to 5593', open 2 hours, SI 20 minutes, fair blow, recovered 90' sl/OCDM. Recording bomb was destroyed men bottom packer was jarred loose from hole.

No Pressures:

DST #8 5586' to 5610', Mis-run. Packer failed.

DST #9 from 5584' to 5610', open 2 hours, good blow increasing to strong, gas in 15 minutes, recovered 150' sl/OCDM.

Pressures:

IFP. 125#
FFP. 200#
BHSIP (20 min.) 1800#

DST #10 from 5628' to 5644', open 1½ hours, SI 20 min. weak blow for 15 minutes then died, recovered 10' DM.
No Pressures.

9

5575', open 2 hours, SI 20 minutes,
fair blow, recovered 90' sl/OCDM. Recording bomb was
destroyed men bottom packer was jarred loose from hole.

No Pressures:

DST #8 5586' to 5610', Mis-run. Packer failed.

DST #9 from 5584' to 5610', open 2 hours, good blow
increasing to strong, gas in 15 minutes, recovered
150' sl/GCDM.

Pressures:

IFP. 125#
FFP. 200#
BHSIP (20 min.). 1800#

DST #10 from 5628' to 5644', open 1½ hours, SI 20 min.
weak blow for 15 minutes then died, recovered 10' DM.
No Pressures.

DST #11 from 5927' to 5962', open 1½ hours, strong blow,
recovered 3040' gas in drill pipe, 290' very heacily
O&GCDM, 720' very heavily oil & sl/GC muddy SW.

Pressures:

IFP. 200#
FFP. 525#
BHSIP (20 min.). 1700#

DST #12 from 5960' to 6002', open 1½ hours, strong blow,
recovered 990' sl/O&G muddy SW.

Pressures:

IFP. 125#
FFP. 525#
BHSIP (20 min.). 1550#

Columbian Fuel Co. P. H. Ranch
10-335-31W S. W. & Co

9
BEST COPY
AVAILABLE