

1-331W

MAP NO. 84

STATE Kans. COUNTY Seward

SEC. 31-33S-31W

OPER. Anadarko Prod. Co., Liberal, Kansas

LOC. 100' No of C SE NW

WELL #1 FARM Davies "C" Arkalon

FT/FR LINE

CO. Moran Bros. Drlg. Tools

ELEV. 2547

GR. 2556

FT/FR

LINE 2558 KB

INT. 6000' Miss Test

GEOL.

F.R. 9/13/63

SPUD

9/16/63

COMP.

1/28/64

TD 6318

FM.

St. Louis

PBD.

Completion Record

PRODUCING FM.

FROM

TO

PERF W/HOLES

TREATMENT

Morrow

5636-5657

68

500A & Frac

I.P. Cal O.F.; 16,900,000 Cfgpd (no press)

Casing Record

8-5/8" @ 1386 w/725 sx.

4 1/2" @ 5730 w/110 sx.

Data Inc.

GR Log Tops & Datums

No upper tops picked

Tor	4162	-1615	Mrw	5517	-2970
Lans	4290	-1743	L/Mrw	5631	-3084
Marm	4990	-2443	B/sd	5661	-3114
cher	5144	-2597	Miss	5661	-3114
			St G	5960	-3413

St L	6075	-3528
RTD	6310	-3763
LTD	6318	-3771

PTD 1356, rng logs prior to rng S.P.

DST #1 (Morr) 5617-80, Pkr failed

DST #2 (St L) w/5 pkrs. 5990-6210, Op 10", Op 35", R 180' M,

ISIP 2047#/40", IFP 50#, FFP 90#, FSIP 1837#/40"

RTD 6310 (Miss) E Log to 6318, 4 1/2" @ 5730 w/110 sx., MICT

(Drilled in tite, hooked to flow) 12/5654-57 (Morr) no sho nat,

500A, Ga 540,000 cfgpd, SI/13 hrs, Ga 725,000 cfgpd, 56/5636-50

(Mrw) Ga 1,300,000 Cfgpd, Frac (15,000 Jell A x 12,000# sd)

Ga 5,020,000 Cfgpd, 1 Pt. Cal OF 16,900,000 Cfgpd, Mrw 5636-5657

COMPLETE (11/4/63)

