

15-175-10017-0000

DRILLER'S LOG OF
CABOT CORPORATION
No. 1-A H.C. Bryant
Seward Co., Kansas

Company:	Cabot Corporation	Commenced:	3-8-64
Farm:	H.C. Bryant #1-A	Completed:	
Location:	1980' FNL & 660' FWL	Contractor:	R.W. Rine Drlg.
	Section 8-33S-33W	Elevation:	2835' GR
Casing:	13-3/8" @ 70' (100 sacks		2845' DF
	8-5/8" @ 2750' (200 sacks		2848' KB
	5-1/2" 6019' (200 sacks	Total Depth:	6380' Driller
			6382' Electric log

Prod:

0 to 320' Sand & Gravel & Red Rock
320 to 720' Red & gray shale
720 to 1200' Red shale & gyp
1200 to 2200' Red shale
2200 to 2610' Gray shale & anhydrite
2610 to 2750' Anhydrite & dolomite
2750 to 2900' Dolomite & broken lime
2900 to 3430' Broken lime
3430 to 3930' Gray chalky lime
3930 to 4110' Gray shale
4110 to 4310' Dark gray shale & lime streaks
4310 to 4590' Broken lime
4590 to 4695' Broken lime
4695 to 4820' Hard gray lime
4820 to 5070' White lime
5070 to 5400' Gray & brown lime
5400 to 5622' Brown lime & dark gray shale
5622 to 5656' Gray shale
5656 to 5742' Sand & shale
5742 to 5820' Gray shale
5820 to 5846' Sand
5846 to 6010' Shale & sand
6010 to 6130' Broken sand
6130 to 6250' Hard gray lime
6250 to 6290' Sandy lime
6290 to 6380' White lime T.D.

FORMATION TOPS:

Top Morrow	5622'
Morrow Sands	5654-68'
" "	5670-80'
Mississippian	5836'

PERFORATIONS:

5667-68' (Morrow Sand) → *squeezed off*
5676-80' (Morrow Sand) → *squeezed off*
5678' 4 holes open.