

Seward County - Kansas

Seeley #1
Seward County

Seeley #1 - Seward County Oil & Gas Company

NE corner of NE $\frac{1}{4}$ of Sec. 20; T-33-S; R-33-W.

Total depth - 2427 ft.

Formation	Thickness	Depth	Remarks
Brown sandy clay		135	
Water sand	50	185	
Sandy clay	20	205	
Water sand	50	255	
Brown clay	15	270	
Sand	45	315	
Clay	34	349	
Fine gray sand	31	380	
Yellow clay	20	400	
Blue mud	40	440	
Sand	5	445	
Red bed	425	870	
Red sand	10	880	
Red bed	48	928	
Lime or white chat	12	940	
Red bed	15	955	
Hard lime	10	965	
Red rock	5	970	
Lime or white chat	30	1000	
Blue mud	5	1005	
Red rock	95	1100	
Fine red sand	150	1250	
Red bed	350	1600	
Red sand and lime	55	1655	
Blue mud	5	1660	
Red Bed	10	1670	
Blue mud	10	1680	
Red bed	85	1765	
Water sand	45	1810	
Red Bed	125	1935	
Blue shale	5	1940	
Red bed	145	2085	
Blue shale	15	2100	
Gray sandy lime	10	2110	
Blue shale	60	2170	
Shale and lime	12	2182	
Blue shale	18	2200	
Gray shale and lime	50	2250	
Sand and lime	5	2255	
Blue and gray shale	20	2275	
Blue shale	12	2287	
Gray sandy lime	6	2293	
Blue shale	7	2300	
Gray lime	6	2306	
Blue shale	4	2310	
Gray sandy lime	50	2360	
Blue sandy lime	35	2395	

<u>Formation</u>	<u>Thickness</u>	<u>Depth</u>	<u>Remarks</u>
Blue shale	5	2400	
Gray sandy lime	10	2410	
Blue shale	5	2415	
Sand and lime		2427	Heavy flow of gas.

Bad fishing job encountered. Still fishing and trying to clean hole on August 30, 1923. Two string tools taken out of hole and some casing, now drilling up iron at 1520 ft. 8/30/23.