

4-1491 Map No. K-84
 OPER GULF OIL CORP
WICHITA, KS.
 WELL #1 ALEXANDER HEIRS
E.F. WAKEFIELD
 FIELD ARKALON WEST (MRW & MISS GAS)
 I.P. CAL OF 4,134,000 CFGPD & 2½ B COND/PD,
MRW 5758-85



S-T-R 33-33S-32W
 SPOT APP C SE NW
 CO SEWARD (KS)
 ELEV 2690 KB

(KB LOG)
 LAN 4412 -1722
 CHER 5220 -2530
 MRW 5602 -2912
 U/MRW LM 5664 -2974
 B/LM 5680 -2990
 MRW LM 5738 -3048
 B/LM 5752 -3062
 MRW SILT-STN 5754 -3064
 B/SILT 5756 -3066
 MRW SD 5778 -3088
 B/SD 5801 -3111
 CHES 5807 -3117
 STE G 6065 -3375
 LTD 6149 -3459
 RTD 6150 -3460

SPUD (3-7-66) 20" CONDUCTOR @47' W/140 SX.
 8" 1508 W/675 SX. BOB DREYER - GEOL
 NO DST'S, NO CORES, RTD 6150, WELEX LOG, 4½" 5917 W/125 SX.
 CO 5877, PE 6/5782-85, 6/5758-61 (MRW), NTN, FRAC
 30,000 GELL 3% A X 25,000# SD, 8 PT LD, GA 1.790,000
 CFGPD, GA 2,060,000 CFGPD + 35 BLW/7 HRS
 HI RATE/5-PT TST, GA 1,435,000 CFGPD, FTP 1228 & FCP 1301#
 CAL OF 4,134,000 CFGPD + 2½ B COND PD, SIBHP 1818#/162 HRS
MRW 5758-85 COMPLETED

Data Inc

MISCEL DATA
 GEOL BOB DREYER
 FTG 2080' FNL X 1980' FNL OF NW/4
 SUPPT 20" CONDUCTOR @47' W/140 SX.
 CSG 8" 1508 W/675 SX. 4½" 6917 W/125 SX.
 ELEV 2688 DF
2679 GR
 SPUD DATE 3-7-66
 DRLG COMP 3-4-66
 FR by DATA 4-21-66
 COMP by "

LIBERAL ELECTRIC LOG TOPS

2690 KB

Winfield 2642 (448)
Heebner 4242 (-1552)
Toronto 5264 (-1574)
Lansing 4404 (-1714)
Marmaton 5068 (-2378)
Morrow 5594 (-2904)
"S-3" 5754 (-3064) 6/12;
"S-3" 5776 (-3086) 18/34 4,134 MCF / 2½ BCondPD
Chester 5802 (-3112)
Ste. Gen 6076 (-3386)
TD 6150