

MAY 8 0 1980

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 175 — 20,456
County NumberOperator
Anadarko Production CompanyAddress
P. O. Box 351, Liberal, Kansas 67901


Well No. 2 Lease Name ETZOLD "B"

Footage Location
660 feet from NW (S) line 660 feet from NE (W) linePrincipal Contractor Geologist
Lohmann-Johnson Drilling Co. Joe BlairSpud Date Date Completed Total Depth P.B.T.D.
3/13/80 5/9/80 6466' 6400'Directional Deviation Oil/Gas Purchaser
1 deg @ 6446' Diamond Shamrock

S. 22 T. 33S R. 34 XBX W

Loc. C SW SW

County SEWARD

640 Acres
N

Elev.: Gr. 2898'

DF 2908' KB 2909'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1675'	Pozmix Common	600 200	3% CaCl
Production	7-7/8"	5-1/2"	15.5#	6445'	Litewate Pozmix	110 110	ss .05% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46	6244-66'

Size	Setting depth	Packer set at
2-3/8"	6290'	


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/2000 gal 15% MCA	6244-66'
F/40,000 gal Versa-gel + 56,500# 20-40 sand	6244-66'

INITIAL PRODUCTION

Date of first production 5/12/80	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 151 bbls. Gas 162.3 MCF Water 99 bbls. Gas-oil ratio 1074 CFPB
Disposition of gas (vented, used on lease or sold) To Be Sold	Producing interval(s) 6244-66'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 2	Lease Name ETZOLD "B"	Oil	
S 22 T 33S R 34 ^{XB} W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME DEPTH
Sand and Redbed	0'	1348'	
Redbed	1348'	1659'	
Anhydrite	1659'	1676'	
Redbed and Shale	1676'	1920'	
Shale	1920'	2245'	
Lime and Shale	2245'	6446'	
Cored from 6240-99', rec 59'.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Paul Campbell, Division Production Manager Title May 19, 1980 Date		