

KANSAS DRILLERS LOG

API No. 15 — 175 — 20,344
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

1

Lease Name

GUTTRIDGE "B"

Footage Location

660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor

Lohmann-Johnson Drlg Co. Inc.

Geologist

Joe Blair

Spud Date

1/21/78

Total Depth

6370'

P.B.T.D.

6368'

Date Completed

3/17/78

Oil Purchaser


Apco Oil Corp.

S. 29 T. 33S R. 34 E W

Loc. 660' FN & WL

County Seward

640 Acres
N



Locate well correctly

Elev.: Gr. 2937'

DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1704'	Poz Common	600 200	4% gel, 2% cc 3% cc
Production	7-7/8"	4-1/2"	10.5#	6369'	Lite-Wate S. S. Poz	100 100	.5% .5% CFR-2 + 12-1/2# Gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		6295-6302'
Size	Setting depth	Packer set at			
2-3/8"	6298'				


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Loaded hole w/20 bbls 2% KCL wtr; A/2500 gals 15% NE, F/36,500 gals Versa Gel + 59,250# 20-40 sd.	6295-6302

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
3/12/78		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	120 bbls.	53.6 MCF		446.7 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Vented			6295-6302' B/Chester		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ANADARKO PRODUCTION COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL	
Well No. 1	Lease Name GUTTRIDGE "B"		
S 29 T 33 S R 34 ^W _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Sand	40'	160'	
Sand & Redbed	160'	1177'	
Sand, Redbed & Dolo	1177'	1705'	
Redbed & Shale	1705'	2678'	
Lime & Shale	2678'	6370'	
TOTAL DEPTH		6370'	
Core #1 6208-66', rec 57'. Core #1 10' Sh Lm, 4' Lm, 32' Sh Lm, 4' Sh.			
Core #2 6266-6312', rec 46', 2' Brn Lm, 11' Sh, 17' Brn Lm-Sd, good show, 13' Lm, spotted show, 2' Brn Lm, NS.			
DST #1 6292-6370 (Chester) 30-90-30-120, op tool w/vry wk blo, 2nd op wk blo incrg to strong, rec 120' DM, 90' GCDM w/ SO, 30' G&OCDM.			
Results of sample chamber DST #1: Chamber Press 45#, rec .413 CFG, 1020 cc oil, 680 cc DM, no wtr, API Grav 40.8 60°, Cl mud recd 1200, pit mud 1200.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Paul Campbell, Division Production Manager Title June 13, 1978 Date		