


JUL 10 1971

DRILLERS LOG

MARCH NO. 1

KANSAS



Elevation: 2880' KB

CASING RECORD: OPERATOR: Beacon Resources Corp. DESCRIPTION: 150' South of
8-5/8" @ 1604' CONTRACTOR: Sage Drilling Co. C NW NE
w/650 sax cement COMMENCED: December 15, 1970 Sec. 12-33S-34W
TOTAL DEPTH: 4410' COMPLETED: December 24, 1970 Seward County,
Kansas
FLO 40 BOPD & 30 BWPD & 150,000 CFGH
TOR & LKC

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	500	
Red Bed & Shale	500	670	
Red Bed, Gyp & Sand	670	1400	LOG TOPS:
Red Bed & Shale	1400	1570	
Anhydrite	1570	1605	*Anhydrite 1570
Lime, Shale & Red Bed	1605	1911	Heebner 4187
Lime & Shale	1911	2550	Toronto 4211
Lime	2550	2807	Lansing 4332
Lime & Shale	2807	3032	*Sample Top
Lime	3032	3460	
Lime & Shale	3460	4213	
Lime	4213	4235	
Lime & Shale	4235	4241	
Lime	4241	4410	5 1/2" @ 4409' w/100 sax cement

I certify that this is a true and correct copy of the above log to the best of my knowledge.

DST #1 4213-35
DST #2 4228-4242

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 28th day of December, 1970.

Louise K. Whitted