

SCOUT TICKET

COUNTY	Clark	STATE	Kansas	DATE	10/31/54
COMPANY	Mid-Continent				
FARM	Gibson	NO.	3		
SEC.	35	TWP.	33	RGE.	21
Location in Sec.					ELEV. 1954 DF
Fr. N.		Fr. S.		1949 DF	
Fr. E.		Fr. W.		1939 DF	
C of NW SW					

PERFORATIONS	GAS PAYS	20"	CASING RECORD
	Hollenberg	13' 3/8"	75 (250)
	Herington	10%	509 (500)
	Padock	9 3/4%	2455 (750)
	Krider	7"	
	Odel	6"	
	Winfield	5 1/2"	5562 (300)
	Gage	TD	
	U. Ft. Riley	PB	
	L. Ft. Riley	Nat	
		Acid	
		AA	
		DEL	
		Rock	

Contractor H & P Tools

10/28/54 Location

NOV. 4 1954

NOV. 11 1954

NOV. 18 1954

WOC

4365 open 3.5 min

DST 4847-57 1 week below for 20 min

& died rec 12' mud FP

BHP 1900# (20)

NOV. 25 1954

DEC 3 1954

5456-71 rec 15'

1' Ls red dense

1 1/2' Ls shly

1/2' sh Lt GRY s.d.y

1' sd Lt GRY shly. lite, MS

2' " GRY fine micaceous, lmy, lite

sh para saturated

1' " as above Lam shly sh

1' " " " laminated MS

2' sh BK w/ thin sd seams

2' sd Vy fine laminated w/ BK sh

w/ shly sh

4 5471-96 Rec 25'

1' sd Gry fine micaceous w/ BK
sh lam sli show oil
2' sh BK w/ waxy thin seams
Gry fine sd w/ fl. oil
6' sd Gry fine lite w/ BK sh
seams

1' sd as above Quartzite
1' sd Gry fine BK sh lamination
sli show oil
4' sd Gry heavy lite shaly sli sd
8' sd Gry fine same sh lamination
w/ sli sd

2' sd as above fr oil
A 5496 - 5526 Rec 30'
1' sh BK w/ fr fine Gry sd
1' sh Gry sdy Pyritic
12' sh Drk Gry - BK rotten
3' sdy sh Gry - BK waxy rotten
1' sd Gry fine lite shaly
4' ls Pink lss dolitic sli
sdy loss NO Para
6' ls Pink fine xlm w/ loss
dolitic w/ sli sdy sli
Para NO show
2' ls Pink lss xlm w/ loss
sli dolitic NO Para
1' sh Gry waxy sli Calc

DST 5454-96 Lkr strong - weak blue
Rec 770' sli 0.6 CM FP 345-445'
BHP 1045' Tool sli ply

RTD 5563 Sch 1

M.I.T. 10.5536

56 5476-90

DEC 9 1954

A 1250 mud
F 19600 9600# sd
5/0 Flowed 21 BOPH for 18 hrs
13 BOPH 1/2" choke

DEC 16 1954

" 13 1/2 BOPH 1" ch
TP 50# CP 675#
STP 500 SICP 1400#

Flowed 85 BD in 8 hr 3/4" ch
Calc 255 BOPD

STP 525 SICP 1525

+