

A-7-49
MAP NO. 84
STATE Kansas COUNTY Seward SEC. 35 Twp 33S Rge 31W
ELEV. 2725 DF
OPERATOR Shamrock Oil & Gas LOC. NW NE
WELL NO. 2 FARM NAME Simonson "A" FT. FROM _____ LINE
OO. Kismet (PD 6000) FT. FROM _____ LINE
FR. 6-2-61 SPUD 5-27-61 COMP. 7-5-61
CONT./GEOL. D & M Rig #3

COMPLETION RECORD
NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD
a St Louis 5818-95 16 1600 Ac

b

c

d

d I. P. OIL/DIST. F/325 BORD GAS _____ M.C.F.P.D. _____ CHK. 3/8" HRS. 24
b " " (Calc fr 8 hr tst) " " "
c " " " " " "
d

SIP# _____ FI TP # 135 FI CP# _____ SIBHP _____
GOR. _____ GR. 37° PBDT _____ TD 5952

CASING - CEMENT RECORD
SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
9-5/8" 1545 750
5-1/2" 5952 400

OPERATOR Shamrock Oil & Gas WELL NO. #2 Simonson "A" ELEV. 2725 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Lower Lansing	4868		Council Grove	3063	338
			Lansing	4398	
			Marmaton	5039	
			Cherokee	5201	
			Morrow	5522	2797
			St Louis	5818	3093

Spud 5-27-61. 9-5/8" @ 1545 w/750 sx.

DST #1 (Lansing) 4875-96, op 90 mins, Gd blo, GTS at end, TSTM,
Rc 55 HG&SOCM / 270' HG&OCM / 270' HG&OCMW / 450' GCW, ISIP
1810/30 mins, FP 220-510, FSIP 1655/30 mins, HSH 2695-2430.

RTD 5952, logs.

5-1/2" @ 5952 w/400 sx. MICT.

Ran Corr log from 5897-5397.

Perf 2 each @ 5895, 5892, 5888, 5856, 5837, 5829, 5826, 5818.

Treated each perf w/200 Ac. (Total 1600 Ac).

2-3/8" tbg @ 5825, FL 1500 fr Surf, Flod 64 BF w/GSO&G/5 hrs.

Swb 34 BF. KO. Flod 23 BF (75% oil)/2 hrs, 3/4" ck, FCP 10.

Flod 21 BO/1 hr, (Gty 37°), 1/2" ck, FTP 70, FCP 75. Flod 14

BO/1 hr, 1/2" ck, FTP 50, FCP 100. Flod 27 BO/2 1/2 hrs, 3/8" ck,

FTP 80, FCP 130, 10,000-7 $\frac{1}{2}$ % Ac, swb 84 BL/3 $\frac{1}{2}$ hrs. KO. flod
 74 BF (90% oil)/3 $\frac{1}{2}$ hrs, 1/2" ck, FTP 110. flod 100 BO/3 hrs,
 3/4" ck, FTP 80, FCP 0. flod 52 BO/2 $\frac{1}{2}$ hrs, 1/2" ck, FTP 110,
 FCP 0. flod 52 BO/1 $\frac{1}{2}$ hrs, 3/8" ck, FTP 130, FCP 0. fold 220
 BO/12 hrs, 1/2" ck, FTP 124, FCP 100.

IP flod 108.2 BO/8 hrs, 3/8" ck, FTP 135, Gty 37°, calc
 325 BOPD from St. Louis 5818-95.

CSO

Elw 2778 L-3

HB 4260 - 1532

TA 4276 - 1548

Lma 4398 - 1670

Mym 5040 - 2312

mo 5522 - 2794 N 55544-

Ch 5624 - 2896

st 6 5666 - 2918

Sto 5770 - 3022

TD 5952

58 74
 27 31
 27 31