

A-10-44

MAP NO.

STATE KansasCOUNTY SewardSEC. 35ELEV. 2730 KBOPERATOR Shamrock Oil & Gas Corp. Twp 33S Rge 31WWELL NO. 4 FARM NAME Simonson "A" loc. C SW NEOOL Kismet

(PD 6000)

FR. 8-3-61SPUD 8-5-61COMP. 9-28-61

FT. FROM _____ LINE

FT. FROM _____ LINE

CONT./GEOL. D & M Drilling Tools

NAME PRODUCING INTERVAL

COMPLETION RECORD

a. TorontoFROM - TO 4296-4300PERF. W/HOLES 8

TREATMENT RECORD

250 Acb. MississippiansFROM - TO 5839-5926PERF. W/HOLES 1410,500 Ac

c.

d.

a. I. P. OIL/DIST. P/136BOPD (Calc fr 6 hr tst)b. " P/214BOPD (Calc fr 20 hr tst)

c.

d.

CHK. P HRS. 24" P " 24

" " "

SIP#

FI TP #

GOR.

GR. 41° (a) : 36° (b)

FI CP#

D & A ()

SIZE 9-5/8"DEPTH 1550

CASING - CEMENT RECORD

W/SAX. 750

SIZE

SIBHP

TD 6000

7"

6000

200

DEPTH

W/SAX.

OPERATOR Shamrock Oil & GasWELL NO. #4 Simonson "A"ELEV. 2730 KB

SAMPLE TOPS

DEPTH

SUB SEA

ELEC. TOPS

DEPTH

SUB SEA

Toronto

4287

Lansing

4408

Marmaton

5050

Cherokee

5215

Morrow

5539

Ste Genevieve

5688

St Louis

5848

Spud 8-5-61. Set 9-5/8" @ 1550 w/750 sx. @ 3459, fished out DP.
 DST #1 (Toronto) 4291-4302, op 90 mins, GTS/5 mins, ga 221 MCF,
 TSTM/90 mins, Rc 735 GO, ISIP 1295/30 mins, FP 80-280, FSIP
 1190/30 mins, BHTs 112° F.
 DST #2 (Lansing) 4898-4914, op 90 mins, Rc 1010' SW, ISIP 1580/
 30 mins, FP 105-495, FSIP 1505/30 mins.
 RTD 6000, logs. 7" @ 6000 w/200 sx. MICT.
 P/2 each @ 5839, 5841, 5850, 5854, 5857, 5860, 5864, 5899, 5900,
 5902, 5904, 5908, 5918, 5921, 5924, 5926, 2000-15% Ac. Swb
 31 BO / 248 BL/21 hrs, CP 250. Set ret BP @ 5875. Swb 244 BO/
 24 hrs, SQ 5839-5926 w/100 sx. CO to 5872.

Re-P 2 each @ 5839, 5850, 5854, 5857, 5860, 5864, A/500-
15% ac, swb 46 BO/23 hrs, 10,000-7½% ac, swbd ld + 28 BNO/
26 hrs, set prod pkr @ 5804, set BP @ 4340.
P 16/4294-4302, 1000-15% ac, swb ld/NS. SQ 4294-4302 w/100 sx.
CO 4321.

P 8/4296-4300, 250 Ac, swb 32 BO/20 hrs, CO 5872, ran dual
tbg. 2 3/8" @ 5804 & 2 3/8" @ 4292.

POP.

IP Pump 44 BO/6 hrs, calc 136 BOPD, Gty 41°, from Toronto
4296-4300.

IP Pump 178 BO/20 hrs, calc 214 BOPD, Gty 36° from Mississippian
5839-5926. 9/28/61

LIBERAL LOG TOPS

2730

Winfield 2715 (+15)
Council Grove 2968 (-238)
Heebner 4276 (-1546)
Toronto 4292 (-1562) tst G & O; Ø pmp 44 BO/6 hrs
Lansing 4408 (-2278)
Marmaton 5062 (-2332)
Morrow 5540 (-2810)
Chester 5656 (-2926)
Ste. Gen 5700 (-2970)
St. Louis 5864 (-3134) Ø 178 BO/20 hrs
TD 6000