

90115

OWWO

11-143W + MAP NO. 837
STATE Kansas COUNTY Stevens SEC. 14-33S-36W
LOC. C SE NW

OPER James F. Smith, Amarillo, Tex. FT/FR LINE

WELL #1 FARM Brown FT/FR LINE


POOL WC ELEV. GR. 3048 0 DF 3051 E, KB

CONT. Mahoney Drlg. GEOL. Mark Williams

INT.

F.R. 9-12-63 SPUD. Old 8-23-59 COMP. 11-12-63

TD 6349 FM. St. Gen PBD. 6570



Completion Record

PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
Morrow	6035	- 66	7	3500A & Frac
I.P. 4 pt. C.O.F. 840,000 Cfgpd (SIP 1389#)				

Casing Record

4 1/2" @6600' w/220 Sx. DV tool @3100' w/150 Sx.

Data Inc.

Spl Tops: (DF)		Old Log Tops (DF)	
Hb	4253	Win	2713 + 335
Tor	4334	CG	3007 + 41
Lans	4398	Neva	3140 - 92
Marm	5008	Hb	4164 -1116
Morr sd	6008 -6060	Tor	4170 -1122
D	6349	Lan	4274 -1226
		D Mo	5042 -1994

New Info:

St.L	6420	-3372	Cher	5286	-2238
NSO/G			Morr	5744	-2696
DDRTD	6600	-3552	Morr sd	6009	-2961
			B/"	"	6060 -3012
			Chest	6080	-3032
			St. G	6290	-3242
			LTD	6350	-3302

OLD INFO:

Was Shell Oil #1-14 A&C Brown, Old Spud 8-23-59.
DST #1(Morr)6016-60, Op 1 hr, FB, 65' SGCM, ISIP 200#/60', IFP 35#
FFP 45#, FSIP 375#/60'. OTD 6349, D&A -COMPLETED 9-16-59

NEW INFO: (9-10-63)

RT, DD 6600' TD, (St. L)NSO/G, 4 1/2" @6600' w/220 Sx. DV tool
100' w/150 Sx. GRN Log. MICT. CO 6570', Perf Morr sd 2/6035-37
4/6049-53, 1/6066-, \$ dry, NSO, SI/12 hrs, no press, 1000A(10%)
Ga 108,000 Cfgpd/NT, 12 hr, SIP 1000#, 2500A(7 1/2%) + 5 ball sealers
Ga 190,000 cfgpd/NT, 12 hr. SIP 1250#, Frac (20,000A x 20,000 sd)
ga 500,000 Cfgpd/18 hrs, + small amt. wtr. SIP 1150#/12 hrs. Ga
860,000 Cfgpd + spray cond. & AW/90', SIP 1450#, 96 hrs. Ga. 1,
200,000 cfgpd/1 hr, Ga 760,000 Cfgpd + 1/2 BWP/NT, SIP 1450#/64 hr\$
Ga. 1,400,000 cfgpd, 1 hr. Ga 1,200,000 cfgpd, 2nd hr. (Cont)

