


Re-issued to include Additional Log Tops.

MAP NO. _____ A-5-163 ELEV. 1830DF
 STATE Kansas COUNTY Clark SEC. 36 Twp 33S Rge 22W
 OPERATOR Falcon Seaboard Drlg. Co.-Tulsa LOC. C NE SW
 WELL NO. 2 FARM NAME Pfeifer FT. FROM _____ LINE _____
 POOL Harper Ranch, Ext. (PD 5600) FT. FROM _____ LINE _____
 FR. 2-6-61 SPUD. 2-6-61 COMP. 4-10-61
 CONT./GEOL. Herndon Drlg. (Tulsa)



NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
	FROM - TO	PERF. W/HOLES			
a	Morrow	5362-71	36	500Ac, F/10x30	
b					
c					
d					

I. P. OIL/DIST.	WTR.	COF	GAS	13,100	M.C.F.P.D.	CHK.	4 pt	HRS.	24
b	"	"	"	"	"	"	"	"	"
c	"	"	"	"	"	"	"	"	"
d									

D & A ()

GOR.	GR.	PBTD	TD
			5441

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
13 3/8"	205	250			
5 1/2"	5440	300			

OPERATOR Falcon-Seaboard Drlg WELL NO. #2 Pfeifer ELEV. 1830 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Elgin	4068	
			Heebner	4218	
			Toronto	4266	
			Brown Lime	4448	
			Lansing	4460	
			Marmaton	5036	
			Morrow	5318	
			Morrow Sand	5362-72	
			Chester	5384	
			Ste Genevieve	5412.	

5318

Spud 2-6-61, 13 3/8" @ 205 w/250 sx.
 DST #1 (Morrow) 5366-77, op 2 hrs, GTS 2 1/2 mins, FSTM, RC 10' mod, ISIP 1980/30 mins, FP 15-15, FSTP 1955/15 mins.
 RTD 5441, logs, 5 1/2" @ 5440 w/300 sx.
 P/36/5362-71, 500 MA, Frac 10,000 X 30,000 sd, rc 1d.
 IP 4pt COF 13,100 MCF, SIP 1665, from Morrow (5362-71).
 COMPLETE 4-10-61.