


11-103
 MAP NO. K-84 ELEV. 2727DF 2729KB
 STATE Kans COUNTY Seward SEC. 36 TWP. 33S RGE. 31W
 OPERATOR Shamrock Oil & Gas Co. LOC. C SE NW
 WELL NO. 3 FARM NAME Raymond E. Pope FT. FROM _____ LINE _____
Kismet FT. FROM _____ LINE _____
 FR. 9/11/61 SPUD 9/1/61 COMP. 11/9/61

CONT./GEOL.		COMPLETION RECORD		TREATMENT RECORD	
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES			
a <u>Tor</u>	<u>4302-08</u>	<u>12</u>		<u>1000 A</u>	
b <u>Up. Lans</u>	<u>4419-25</u>	<u>12</u>		<u>3500 A</u>	
c <u>Miss</u>	<u>5772-5840</u>			<u>6000 A</u>	
d	(Triple completion)				



d I. P. OIL/DIST. _____ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. _____
 b .. State Pot: P 62 BO + .14 1/2 BW, (Grav 40 deg), 24 hrs. Tor.
 c .. State Pot: P 80 BO + .20 BW, (Grav 40 deg), 24 hrs. Lans
 d .. State Pot: Cal P 529 BO, NW, (Grav 37.3 deg), 24 hrs, Miss

SIP#		FI TP #		FI CP#		SIBHP	
GOR.		GR.		PBD		TD	
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.		
<u>9 5/8"</u>	<u>1556</u>	<u>750</u>					
<u>7"</u>	<u>5980</u>	<u>250</u>					

OPERATOR Shamrock Oil & Gas WELL NO. 3 Raymond E. Pope ELEV. 2727 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
RTD (Miss)	5980	-3251	CG	3094	- 365
			Tor	4295	-1566
			Lans	4410	-1681
			Marm	5050	-2321
			Morr	5535	-2806
			St Gen	5617	-2888
			St Lou	5785	-3056

DST #1 (Tor) 4300-4311, Op 90", R 30' Oil + 540' MCO + 90' GCO, no IBHP, IFP 40#, FFP 120#, FBHP 900#/30".
 DST #2 (Lans) 4419-26, Op 90", GTS/1", Ga 263 Mcfgpd/5" TSTM/20", R 3955' GCO, NW, IBHP 1350#/30", IFP 240# FFP 715#, FBHP 1230#/30".
 DST #3 (St Lou) 4894-4910, Op 90", R 1160' SW, no IBHP IFP 220#, FFP 675#, FBHP 1505#/30".
 RTD 5980. Sj Log. 7" @ 5980 w/250 sx. MICT
 8/5772-76, 22/5788-99, 28/5826-40 (Miss), 1000 15% A, Swb & Flo 336 BF (75% Oil)/17 1/2 hrs, Flo 20 BOPH/NT FTP 50#, FCP 535#, 5000 7 1/2% A, Swb & Flo ld. Swb &

