

4-154w/ MAP NO. K-84 OWWQC FR & COMP SEC. 36-33S-31W
 STATE Kansas COUNTY Seward LOC. C NW SW
 OPER Texaco, Inc. FT/FR _____ LINE _____
 WELL #1 FARM Gene Black FT/FR _____ LINE _____
 DL Kismet (Multi-Pay) ELEV. 2719 GR. 2724 DF 2727 KB _____
 CONT. Herndon Drlg. Tools GEOL. _____
 CO. Dual Completion
 INT. 4-9-65 SPUD 10-15-61 COMP. 2-27-62
 TD 5905 FM St. Louis 34 PBTD. 5889
 PRODUCING FM. FROM TO PERFS W/HOLES TREATMENT

2.2 # (St G)
24 b (St L)
*

St G	5722-44	34	Nat
St L	5763-5846	203	14,000A
Ca 2,200,000 CFDPD (St G)			
Gas lift 24 BOPD / 9 BLWPD thru 2" ck (St L)			
9-5/8" @1246' w/650 Sx. 7" @5905' w/65 Sx.			

Data Inc.

(Old Spls:)
 Tor 4265
 Lans 4391
 Marm 5042
 St L 5774
 RTD (St L) 5905

OLD INFO: (Same Operator)
 C #1 (Miss) 5762-89, R 27' lm, fn xln, w/
 scat stn & poro, C #2 (St L) 5789-5840, R
 51' lm, fn xln, ool, vug, scat stn & poro
 thru out, bldg oil, C #3 (St L) 5840-85, R
 45' lm, xln, ool, gloc; poro, frac, bldg,
 oil & stained, RTD 5905, Welex Log, 7" @

KB Log (Old)	5905' w/65 Sx., DV tool @4460' w/150 Sx.,
CG	CO 5898 PBTD, Pf 24/5888-5894 (St L), 250
Tor	MA, Acid no go @2000#, Re-acidize w/250MA
Lans	formation no break @2500#, Perf 52/5828-46
Marm	32/5812-20, 117/5763-5802, (St L), Swb 21
Morr	BLO/2 hrs, Swb no new oil or gas/2 hrs, PB
Morr sd	w/frac sd to 5886, Acidize, 5763-5846 w/
Wea St Gen	14,000 gal Gelled 15% Acid, Flo 25 BLO /
Fr St Gen	226 BNO/14 hrs, thru 3/8" ck, FTP 800#, Flo
St L	66 BO / 3 BAW/5 hrs, 3/8" ck, FTP 800#,
LTD	last hr flo 5 1/2 BO / 100 BAW, 1/4" ck, FTP

Log from 4200-5894, St Gen wet from 5720-42, Pf 18/4396-4402 (Lan)
 in tbg w/St Pkrs set @4384-4414, Flo 16 BLO / 17 gal new oil/22
 hrs, on 1" ck, FTP 40#, Gas Ga 392 MCFDPD, after 12 hrs, died,
 Swbd 5 CO, Pull tbg & pkrs @5754, PB w/sd to 5714, Sq 4396-4402 w/
 75 Sx., CO 4558, CO & Pf 4/5020, Sq w/125 Sx. Posmix, CO cem to
 5022, Tst dry, Perf 18/4950-56 (Lans) 2-3/8" tbg w/pkr set @4937,
 Swb 36 B M / 72 BSW/7 hrs, no oil/gas, Swb 18 BSWPH, last 3 hrs, Sq
 Perfs 4950-56 w/125 Sx., Pull tbg & pkr, CO 5898, 18/4878-84 (Lans)
 2-3/8" tbg w/RTTS Pkr @4865, Swb 31 1/2 BSW w/SSG/7 hrs, Sq 4878-84
 w/75 Sx., CO 5898, Re-Perf 16/ 4876-80 (Lans) Ran tbg w/RTTS Pkr

4863, \$ down, tst dry/4 hrs, A/250 + 10 BTrtW + 7 BfreshWFlush,
\$ dn to 4800', swb 48 BXW w/SSO/4 hrs, Sq/4876-80/75 sx.,
2 3/8" Tbg @ 5720 w/pkr @ 5738, flo 83 BO (NW)/5 hrs thru 3/15" ck
TP 600#, GOR 7700:1, G. 35°, St. Lo 5763-5846, Comp. by Texaco
for allow 59 BOPD, State Pot: 2/20/62 (8 hr flo rate) flo 272
BOPD + tr wtr, G. 37.4°, St. Lo 5763-5846 (5888-94 tite)
Completed.

NEW INFO: 1/23/65

TD 5905, PBD 5889, KW/119 BXW, 12/5722-28, 16/5731-39, 6/5741-44
(SG), ran tbg w/str pkrs @ 5750 & 5727, g 1,450 MCF SICP 1200,
SITP 1200/12 hrs, KW w/26 BXW, pull T & str pkrs, set Pkr @ 5752
& circ sleeve @ 5708, \$ 10 BLW, flo 5 BO + 10 BXW/2 hrs, died,
\$ 10 BXW, flo (SG & SL) Pfs, 6,800 MCF + 10 BO + 100 BXW/15 hrs,
FTP 600#, FCP 100#, flo 2,830 MCF, FCP 825#, flo 3,970 MCF, Ste.
Gen perfs flo 750 MCF, FCP 1140, FTP 637, rig gas lift for St.
Lo flo 9 BO + 10 BW/24 hrs, flo 755 MCF (SG), flo 31 BW + SO/24
hrs, (SL) flo 11 BO + 10 BXW/24 hrs, (SL) flo av 10 BOPD + 8
BXWPD (SL), flo 800 MCF, FCP 1050, SG flo 5 BOPD + 10 BWPD
Completed 3/30/65

Flo 24 BOPD + 9 BLWPD thru 2" ck from St. Louis 5763-5846 (Gas
lifted thru 5/64" side door ck) g 2,200 MCF thru 14/64" ck w/
1130# BP from Ste. Gen 5722-44 - First Reported & Comp. 4/9/65.