

2-261W  
MAP NO.

2712GL

ELEV 2716DF 2718KB

STATE Kans COUNTY Seward SEC. 36 TWP. 33S RGE. 31W

OPERATOR Texaco, Inc. LOC. C NE SW


WELL NO. 2 FARM NAME Gene Black FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_

Kismet FT. FROM \_\_\_\_\_ LINE \_\_\_\_\_

FR. 11/20/61 SPUD 11/17/61 COMP. 2/27/62

CONT./GEOL. Herndon Drlg Tools

NAME PRODUCING INTERVAL St Lou FROM - TO 5732-5844 COMPLETION RECORD PERF. W/HOLES 111 TREATMENT RECORD 1000 A



d. Cal Flo I. P. OIL/DIST. 333 BO WTR. NW GAS no Ga M.C.F.P.D. \_\_\_\_\_ CHK. \_\_\_\_\_ HRS. 24

b. " " " " " " " "

c. " " " " " " " "

d. \_\_\_\_\_ D & A ( )

SIP# \_\_\_\_\_ FI TP # \_\_\_\_\_ FI CP# \_\_\_\_\_ SIBHP \_\_\_\_\_ TD 5901

GOR. 3500-1 GR. 37.5 deg. PBDT 5857 CASING - CEMENT RECORD SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_ W/SAX. \_\_\_\_\_

SIZE 9 5/8" DEPTH 1245 650 \_\_\_\_\_

7" 5901 425 \_\_\_\_\_

OPERATOR Texaco, Inc. WELL NO. 2 Gene Black ELEV. 2718 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums			CG	3000	- 282
			Tor	4262	-1544
RTD (St Lou) 5901			Lans	4390	-1672
			Marm	5041	-2323
Gilcrease 50% Working Int.			Morr	5509	-2791
			St Gen	5584	-2866
			St Lou	5730-	-3012
			LTD	5901	-3183

DST #1 (Lans) 4390-4410, Op 1 hr, WB/1 hr, R 30'M, no sho IBHP 125#/30", IFP 76#, FFP 86#, FBHP 163#/45".

DST #2 failed.  
RTD 5901. Ran Log 3000-5901. 7" @ 5901 w/425 Sx. @ DV Tool @ 4483 w/300 sx. MICT, CO 5857 PBDT, 1d w/220 B Crude, Ran Corr Log, 18/5838-44 & 18/5826-32 (St Lou) SD/48 hrs, Ran 2 3/8" tbg w/RTTS Pkr @ 5813. Swb 1d Oil, & Swb dry/4 hrs, 500 (15%) A, Swb 14 B 1d Oil & Flo 137 BNO thru 1/4" ck/12 hrs TP 350#, Killed w/25 BO, 24/5782-90 & 42/5740-54

9/5732-36 (St Lou). Set BP @ 5810 & tbg w/pkr @ 5699. Swb dn to 1500' & flo 7 BO/NW/2 hrs thru  $\frac{1}{4}$ " ck, TP 300#, 500 (15%) A, MP 1100#, Min P 800# @ 4 BPM, flush w/20 BO on vac, swb 14 BLdO & flo 86 BNO + 6 BLd Oil/13 hrs, thru  $\frac{1}{4}$ " ck, TP 875#, Flo 147 BO + 1/2 BXW/21 hrs thru  $\frac{1}{4}$ " ck, TP 850#, GOR 2200-1, flo 115 BO + 1/2 BXW/14 hrs thru  $\frac{1}{4}$ " ck, TP 875# GOR 5000-1, pull BP @ 5810 and tbg pkr @ 5699. ran tbg w/pkr @ 5707, PBSD 5857, Swb dn to 3000' & flo 100 BO/NW/6 hrs thru  $\frac{1}{4}$ " ck, TP 500#, flo 164 BO + 1 BXW/17 hrs, thru  $\frac{1}{4}$ " ck, TP 800#, GOR 3500:1, G. 35°, St. Louis 5732-5832. Field Allow 59 BOPD. State Pot: (2/20/62) (8 hr flo rate) Cal Flo 33 BOPD/NW, G 37.5°. St. Louis 5732-5844.

LIBERAL ELECTRIC LOG TOPS

2719 KB

- Winfield 2722 (-3)
- Heebner 4256 (-1537)
- Toronto 4272 (-1553)
- Lansing 4389 (-1670) tst Mud
- Marmaton 5040 (-2321)
- Morrow 5509 (-2790)
- No Sand (Opr)
- Chester 5560 (-2841)
- Ste. Gen 5594 (-2875) ✓
- St. Louis 5690 (-2971)  $\phi$  333 BOPD
- TD 5900