


✗✗

State Kans. Field W.C.
 Company J. Donoghue County Meade
 Farm FOX No. 2
 Sec. 36 Twp. 33 Range 30

Spot C NE SW

Contractor Gannery

Remarks Gulf DMU



Comm. 1-30-57 Comp. 5-23-57

Elev. DF 2685 GL 2677 KB TD 5879 PB 5830

Pay open hole 5798-5830

I.P. 2.800 MCF Press. 519/605

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5790/350

16" 8 5/8 1472/850

	Sample	Log
5870	Log 4639	MAR 5780
FEB 13	MANM 5281	sd 5788-5804
DST 3250-3310, 6 p/h	MAR 5780	" 5811-32
REC 1080' msw, FP 65-530	sd 5790-5806	MISS 5871
BHP 840/20	" 5810-15	
DST 4509-4613	check 5870	
FEB 20		
DST 4509-4613, 8 p 2,		
REC 60' m + 9409 csw,		
FP 80-760, BHP 1220/20		
DST 5397-5407, 0 p 1 m,		
REC 3' m FP 0, BHP 0/20		
5620		
FEB 27		
DST 5793-5815 op 2 hrs,		
975 25", 50 MCF in 1 hr,		
44 MCF in 2 hrs, REC 92' GLM,		
FP 65-130, BHP 1850/30		
5815-48 REC 33',		
DST 5815-79 op 2 hrs, REC 30' m FP 10-BHP 120/20		
RTD 5879. ran log.		
56" @		

MAR 6 RUCT CO.

MAR 13

✓ shot 86 gts Nitro, g 386 MCF.
A/500m g 386 MCF Prep to fr.

MAR 20

connected Dope from last week

RUCT cu 5830 shot 86 gts Nitro 5798-5830
-CO, g 356 MCF, A/1000m g 358 MCF A/1000m
g 358 MCF fr/30000 sd/15000 126 RD 2,800 MCF
ran T 51,300

MAR 27

MAY 8

APR 10

MAY 15

APR 17

MAY 22

APR 24

SIP 1,605

MAY 1

AMARILLO TOPS

2687 KB

Heebner 4474 (-1787)

Douglas 4484 (-1797)

Lansing 4634 (-1947)

Morrow 5780 (-3093)

"S-2" sd 5788 (-3101) T 16', por 0', @ 2,800 MCF

"S-2" sd 5811 (-3124) T 20', por 20'

Chester 5871 (-3184)

TD 5880 (-3193)