

GERBERDING "A" #3

LOCATION: NE SW NE
DESCRIPTION: Section 36-33S-6W
Harper County, Kansas
SPUDDING DATE: 9-11-58
ROTARY COMPLETED: 9-26-58
INITIAL PRODUCTION: 43 BOPD
ELEVATION: 1299 KB
1296 DF
1291 GR

WELEX TOPS:

Kansas City lime	3790
Base Kansas City	3955
Mississippi chat	4470
Welex T.D.	4563
Driller's T.D.	4560

DST #1 4470-93 Open 2 hrs., gas to surface in 25 min. Rec. 60' VHO & GCM, 520' oil, 20' muddy water.
IBHP 1618# (30 min.), FBHP 1470# (30 min.), IF 62#, FF 220#.

8-5/8" casing set @ 248' w/200 sx.
5-1/2" casing set @ 4559' w/250 sx.

Halliburton Temp. Survey indicates top of cement @ 3480'

CABLE TOOLS: 10-9-58 to 10-13-58

Clean out to 4531'. Perf. 64/4470-86. Bail 1-1/2 bbls. oil/hr.-no wtr. 500 gal. MCA @ max. press. 1150#. After bait back, swab 2-3/4 bbls. oil/hr. POP.

Pumped 50 BOPD, no wtr., for next five days.