

Operator Name Anadarko Petroleum Corporation Lease Name..... Gentzler "A" Well #.... 2H...

Sec..... 7 Twp..... 33 Rge..... 37 ☐ East
☒ West County..... Stevens

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☒ No
 Samples Sent to Geological Survey ☒ Yes ☐ No
 Cores Taken ☐ Yes ☒ No

Formation Description
☐ Log ☒ Sample

Name	Top	Bottom
Surface-Sand	0	364
Shale-Redbed	364	705
Redbed	705	1105
Glorietta Sand	1105	1346
Shale	1346	1930
Lime-Shale	1930	2238
Lime	2238	2685
Lime-Shale	2685	2890
TD	2890	

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface.....	12 1/4	9 5/8	24	700	75/25 Poz Common	250	2%cc + 1/4# cel
Production.....	7 7/8	5 1/2	14	2389	20% DC-D 10% DC-D	40 40	2%cc + 1/4# cel

PERFORATION RECORD

Shots Per Foot Specify Footage of Each Interval Perforated

Acid, Fracture, Shot, Cement Squeeze Record

(Amount and Kind of Material Used)

Depth

.....			
.....			
.....			
.....			

TUBING RECORD

Size

Set At

Packer at

Liner Run

☐ Yes☐ No

Date of First Production

Producing Method

☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain).....

Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity
	Bbls	MCF	Bbls	CFPB	

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented☐ Sold☐ Used on Lease☐ Open Hole☒ Other (Specify) Delayed...☐ Dually Completed☐ Conmingled

GABBERT-JONES, INC.
WICHITA, KAS.

DRILLERS WELL LOG

GENTZLER "A" No.2H
1250' FNL & 2740' FEL Sec. 7-33S-37W
Stevens County, Kansas

COMMENCED: 6/4/87


COMPLETED: 6/7/87

OPERATOR: ANADARKO PETROLEUM CORPORATION


DEPTH From	To	Formation	Remarks
0	364	Surface Sand	Ran 16 Jts. of 24# 8 5/8"
364	705	Shale-Redbed	csg. set @ 700' w/250 sax
705	1105	Redbed	75/25 Posmix 2% CC - 1/4# Floseal
1105	1346	Glorietta Sand	150 sax Class H - 3% CC
1346	1930	Shale	PD @ 9:00 PM 6/4/87
1930	2238	Lime-Shale	
2238	2685	Lime	
2685	2890	Line-Shale	
2890 TD			Ran 72 jts. of 14# 5 1/2" csg. set @ 2889' w/Diecell D - 2% CC - 1/4# Floseal - 40 sax Class C 10% Diecell D - 2% CC 1/4# Floseal - PD @ 11:45 PM 6/7/87

STATE OF KANSAS)
COUNTY OF SEDGWICK) I, the undersigned, being duly sworn on oath, state that
the above Drillers' Well Log is true and correct
to the best of my knowledge and belief and according
to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II - President

Subscribed & sworn to before me this
11th day of June, 1987.


Lola Lenore Costa - Notary Public

My Commission expires 11-21-88